

21 October 2024

Department of Transport and Main Roads (DTMR)  
Wide Bay Burnett Regional Office  
Locked Bag 486  
BUNDABERG QLD 4670  
Att: Helen Stevenson

Dear Helen,

**REFERRAL AGENCY RESPONSE – LIMITED TO ADVICE - RR2024/006/01**  
(GIVEN UNDER S56 PLANNING ACT 2016)

## 1 Application Details

The development application was properly referred to the Gladstone Ports Corporation Limited under section 54 of the *Planning Act 2016* on **25 September 2024**

<b>Application Number:</b>	RR2024/006/01
<b>Applicant Name:</b>	Department of Transport and Main Roads
<b>Applicant Contact Details:</b>	Wide Bay Burnett Regional Office Locked Bag 486 BUNDABERG QLD 4670 Att: Helen Stevenson Email: <a href="mailto:Helen.A.Stevenson@tmr.qld.gov.au">Helen.A.Stevenson@tmr.qld.gov.au</a>
<b>Approval Sought (Port Limits):</b>	<i>Planning Regulation 2017</i>  Part 13, Schedule 10, Division 3 – Table 1 - Prescribed assessable development on land below high-water mark and within the limits of a port under the Transport Infrastructure Act - GPC as the Referral Agency (limited to advice)
<b>Details of Proposed Development:</b>	Operational Works – Prescribed Tidal Works – Scour Protection at Lamington Bridge, Tinana
<b>Location Street Address:</b>	23 Gympie Road, Tinana Qld 4650

<b>Location Real Property Description:</b>	Lot 2 RP92894
<b>Land Owner:</b>	Department of Resources

## 2 Description of Proposed Development

---

Flood remediation works for the Lamington Bridge slope comprising a concrete block retaining wall on a piled foundation. The works are required to increase the structural integrity on the Queensland Heritage Listed bridge (ID600721).

## 3 Referral Triggers

---

This development application was referred to the Gladstone Ports Corporation Limited under the following provisions of the *Planning Regulation 2017*:

Schedule 10, Part 13, Division 3, Table 1, Item 1 –

- a. Prescribed assessable development within limits of a port and
- b. On land below high-water mark and within the limits of a port under the Transport Infrastructure Act

## 4. Details of Referral Response

---

This development application has been assessed against port authority functions under the *Transport Infrastructure Act 1994*, Chapter 8, Part 3 as required in Schedule 10, Part 13, Division 3, Table 1, Item 4 of the *Planning Regulation 2017*.

The Gladstone Ports Corporation Limited requests the Assessment Manager, under section 56(3) of the *Planning Act 2016* to give the following advice stated in Attachment 1.

For further information please contact Trudi Smith, Planning Specialist on 07 4976 1314 or via email [planning@gpcl.com.au](mailto:planning@gpcl.com.au).

Yours sincerely



**Kim Gebers**

**Acting Chief Executive Officer**

Cc: Assessment manager

Enc. Attachment 1: Referral Agency Advice

## Attachment 1: Referral Agency Response (Limited to Advice)

### PART 1: ADVICE

In general the development proposal is in compliance with the requirements of the *Transport Infrastructure Act 1994*. This development approval is subject to each the following advice notes which are stated by GPC, the Referral Agency (limited to advice).

#### Part 1a: Approval sought under *Planning Act 2016* – Prescribed assessable development on land below high-water mark and within the limits of a port under the *Transport Infrastructure Act*

##### General

1. Unless otherwise stated, all conditions must be complied with and completed prior to the commencement of the development.
2. Where additional “approval” is required under these conditions by the Referral Agency (Gladstone Ports Corporation Limited) for drawings or documentation the Applicant must submit for review, amend to the satisfaction of, and obtain written approval from the Referral Agency.

Furthermore, the Referral Agency will require no less than 10 business days, unless otherwise conditioned by the Referral Agency, to initially assess the drawings or documentation provided prior to the commencement of the works. Should further information be required for assessment, the Referral Agency will require a further 5 business days to complete the information request assessment and response.

*Note: Where the Applicant is required to submit further documentation to the Referral Agency, this is to be directed to the Planning section at [planning@gpcl.com.au](mailto:planning@gpcl.com.au), including reference to the allocated referral response number.*

3. The development must be a designed and constructed to mitigate potential adverse impacts to port functions, services and facilities, and to maintain safe navigable access within Port Limits.
4. All development should proceed in accordance with the duty of care guidelines under the *Aboriginal Cultural Heritage Act 2003*. Penalties may apply where duty of care under that Act has been breached.
5. The *Environmental Protection Act 1994* states that a person must not carry out any activity that causes, or is likely to cause, environmental harm unless the person takes all reasonable and practicable measures to prevent or minimise the harm. Environmental harm includes environmental nuisance. In this regard persons and entities, involved in the civil, earthworks, construction, and operational phases of this development, are to adhere to their ‘general environmental duty’ to minimise the risk of causing environmental harm.

##### Engineering

6. Upon completion of the works, the Applicant must supply the Referral Agency with RPEQ certified “As Constructed” plans in both hard copy (2 of) and electronic (CAD format) which illustrate all infrastructure and services installed on, under or over Port limits associated with the activity unless otherwise approved in writing by the Referral Agency.



7. The Applicant must inform the Referral Agency of completion of works within Port Limits within 14 days of practical completion and certify that the site is fit for purpose.
8. Any site lighting used during construction / development should not negatively impact on the visibility of Navigational Aids utilised for the primary shipping channels within Port Limits nor illuminate a landward glare beyond the site boundary. Lighting must be reviewed during construction and use of the development with respect to navigation. Where an issue is identified or a validated complaint received, the Applicant must immediately rectify to the satisfaction of the Referral Agency.
9. Any material which is deposited (not authorised under this approval) or any debris which falls or is deposited within Port Limits during the construction of the approved development shall be removed by the applicant at their cost and expense prior to the commencement of the use of approved structure.

Upon completion of construction, the applicant shall provide the Referral Agency with written confirmation that the waterway is clear of foreign materials not authorised under this approval.


10. If, as a result of the works, or other cause attributable to the Applicant, any bank or tidal structure within Port Limits is displaced (excluding approved works), the Applicant at its cost and expense shall restore the bank or structure to its former condition and take such other action as is necessary to ensure the stability of the bank or structure.
11. Prior to works within Port Limits commencing, the Applicant or their contractor must supply to the Referral Agency for review and approval an Emergency Management Plan for the works within Port Limits for all potential incidents e.g. contaminant spill, riverine flood, adverse weather etc.

#### **Incident Notification**

12. At all times, Gladstone Ports Corporation Environmental Hotline (07) 4976 1617 is to be notified of the occurrence of any:
  - a) Release / spill of contaminants (e.g. fuels / chemicals / sewerage) of any amount to water, and
  - b) Any environmental complaints received by the holder of this approval.
13. Environmental incident notification must be included in any Management Plans for the works within Port Limits.

# RECONSTRUCTION OF ESSENTIAL PUBLIC ASSET (DTMR Event ID:22A)

## 163 Lamington Bridge - Gympie Road 228/163/2835872



DRAWING INDEX		
TMR NUMBER	SERIES NUMBER	DRAWING DESCRIPTION
953830	DI-01	DRAWING INDEX AND LOCALITY PLAN
953831	NL-01	GENERAL NOTES AND LEGEND - SHEET 1
953832	NL-02	GENERAL NOTES AND LEGEND - SHEET 2
953833	NL-03	GENERAL NOTES AND LEGEND - SHEET 3
953834	TC-01	TYPICAL SECTION - SHEET 1
953835	TC-02	TYPICAL SECTION - SHEET 2
953836	GD-01	GENERAL DETAILS - SHEET 1
953837	GD-02	GENERAL DETAILS - SHEET 2
953838	SD-01	STRUCTURAL DETAILS WALL 1A - SHEET 1
953839	SD-02	STRUCTURAL DETAILS WALL B - SHEET 2
953840	SD-03	STRUCTURAL DETAILS WALL 1B - SHEET 3
953841	MD-01	PILE ELEVATION - CONTROL LINE MW300101
953842	CL-01	CONTROL LINE LAYOUT AND SETOUT TABLES
953843	GA-01	GENERAL ARRANGEMENT
953844	LS-01	LONGITUDINAL SECTIONS - CONTROL LINE MW300101
953845	LS-02	LONGITUDINAL SECTIONS - CONTROL LINE MW300103
953846	DD-LD-01	DRAINAGE LAYOUT
953847	DD-LS-01	DRAINAGE LONGITUDINAL SECTION
953848	LR-NL-01	LANDSCAPE NOTES AND LEGEND - SHEET 1
953849	LR-NL-02	LANDSCAPE NOTES AND LEGEND - SHEET 2
953850	LR-NL-03	SETBACKS AND CLEARANCES SCHEDULE - SHEET 1
953851	LR-NL-04	SETBACKS AND CLEARANCES SCHEDULE - SHEET 2
953852	LR-NL-05	SETBACKS AND CLEARANCES SCHEDULE - SHEET 3
953853	LR-NL-06	LANDSCAPE SCHEDULE
953854	LR-LD-01	LANDSCAPE LAYOUT
953855	LR-GD-1	LANDSCAPE SECTION
953856	XS-01	ANNOTATED CROSS SECTIONS - CONTROL LINE MW300101 - SHEET 1
953857	XS-02	ANNOTATED CROSS SECTIONS - CONTROL LINE MW300101 - SHEET 2
953858	XS-03	ANNOTATED CROSS SECTIONS - CONTROL LINE MW300101 - SHEET 3
EARTHWORKS		
953859	EW-LD-01	EARTHWORKS LAYOUT
953860	LS-03	LONGITUDINAL SECTIONS - CONTROL LINE MK300190, 191 & 192
953861	XS-04	ANNOTATED CROSS SECTIONS - CONTROL LINE MK300190 - SHEET 1
953862	XS-05	ANNOTATED CROSS SECTIONS - CONTROL LINE MK300190 - SHEET 2
953863	XS-06	ANNOTATED CROSS SECTIONS - CONTROL LINE MK300190 - SHEET 3
953864	XS-07	ANNOTATED CROSS SECTIONS - CONTROL LINE MK300191
953865	XS-08	ANNOTATED CROSS SECTIONS - CONTROL LINE MK300192
TEMPORARY ACCESS		
953866	CS-LD-01	TEMPORARY ACCESS TRACK LAYOUT
935867	LS-04	LONGITUDINAL SECTIONS - CONTROL LINE MC300110
935868	XS-09	ANNOTATED CROSS SECTIONS - CONTROL LINE MC300110 - SHEET 1
935869	XS-10	ANNOTATED CROSS SECTIONS - CONTROL LINE MC300110 - SHEET 2
935870	XS-11	ANNOTATED CROSS SECTIONS - CONTROL LINE MC300110 - SHEET 3

**SCHEME SUBMITTED** (External Consultants or Internal Business Unit):  
This design meets the requirements of all relevant Australian Standards, Austroads Guidelines and Transport and Main Roads - Policies, References, Standards, Planning and Design Instructions, Guidelines and the requirements of the project brief/functional specifications.

FULL NAME: MICHAEL HARBER      DATE: 19/07/2024  
POSITION TITLE: PROJECT MANAGER      Organisation: AECOM

SIGNED (IF IN WET INK):

**SCHEME SCOPE AND FINANCIAL APPROVAL:** (Regional Director or Delegate):  
I hereby certify that this scheme complies with the intent of the scope and financial limits of the relevant project on QTRIP and the scheme is approved for release in accordance with that program.

FULL NAME:      DATE:  
POSITION TITLE:      Organisation:

SIGNED (IF IN WET INK):



Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title	Date
4 100% Design Issue		19.07.2024
3 85% Design Review		07.06.2024
2 50% Design Review		17.05.2024
1 30% Design Review		04.03.2024

Associated Job Nos	Survey Data	Scales
	Horiz. Datum: GDA2020	NTS
Auxiliary Drg Nos	Horiz. Grid: MGA 56	
	Height Datum: AHD	
	Survey Books: 200418 001, 200418	Dimensions shown in metres except where shown otherwise

228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677
Through Chainage from				

DMTR EVENT 22A DRAWING INDEX AND LOCALITY PLAN			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024

Queensland Government	
Job No.	2835872
Contract No.	CN-21784
Drawing No.	953830 4
Series Number	DI-01 of 01



**GENERAL NOTES**

- The drawings are to be read in conjunction with the following documents:
  - Technical Specifications
  - Supplementary Specifications
  - Tectonic Factual Report Geotechnical Investigation 23329-001-Rev0 dated 12 March 2024
  - AECOM development design Report 60701625-RP-DE-0003
- The contractor is responsible for the design and provision of any temporary works required for permanent works construction.
- All locations, orientation and levels shall be verified on site before commencing any work. Discrepancies shall be referred to the administrator (hold point).
- All dimensions are in millimetres unless noted otherwise.
- Any permits and approvals required for construction of permanent or temporary works shall be obtained by the contractor.
- The contractor is responsible for protection of all existing infrastructure. All damages and reinstatement works shall be done to the satisfaction of the administrator at the Contractor's expense.
- Where trade names have been used for a particular product requirement, equivalent products may be submitted to the Administrator for approval.
- The structures in this package shall be constructed in accordance with TMR Technical Specifications.

**SERVICES**

- Quality Level A survey has been undertaken for services.
- All services must be located, identified and protected before works are carried out in vicinity of retaining walls.

**EARLY WORKS**

- The drawings shall be read in conjunction with the following documents:
  - Environmental management plan
  - Traffic management plan
- Clearing and grubbing shall be in accordance with MRTS04. The site shall be inspected by designer's RPEQ geotechnical engineer to direct extent of works.
- Drainage, erosion and sedimentation control measures shall be in accordance with the environmental management plan.
- Silt retention and temporary surface drainage works shall be in place prior to construction.
- The works shall be constructed in accordance with the Contractor's approved work method statements.

**PROTECTION OF THE WORKS**

- Suitable measures shall be taken to protect the excavated area against inclement weather during construction.
- Areas disturbed for any temporary works / stockpiling shall be reinstated to the existing condition.
- Any damage to the existing pavement or infrastructure during the piling operations shall be repaired by the Contractor at the Contractor's expense.

**EARTHWORKS**

- Measures shall be taken to prevent the uncontrolled fall, roll, topple, slump or slide of debris / slope material arising from the works.
- Excavation shall be carried out to form benches at a maximum slope angle of 1:1.5 U.N.O. Typical excavation detail is provided in the drawings.
- The extent of the works and transition into existing side slopes shall be confirmed on site by the designer's RPEQ geotechnical engineer.
- Excavation of existing rock shall be re-used on site if suitable as approved by the administrator, any excess shall be removed from site.
- The Contractor's RPEQ Geotechnical Engineer shall verify the minimum allowable bearing capacity for base slab foundations and the adequacy of piles embedment into the medium dense sand layer.
- Excavation, backfilling and compaction operations shall be carried out in accordance with the provisions of MRTS04 General Earthworks and MRTS Annexure 04.1
- Procedures and processes for the identification, removal and replacement of any unsuitable materials shall comply with the provisions of MRTS04 clause 9.
- The constructor shall be responsible for maintaining the excavation in a stable condition during construction.
- The constructor shall exercise caution when backfilling, concreting or compacting and shall consider the need for additional temporary supports for sensitive construction activities.

**MASS BLOCKS (KEPPEL BLOCK)**

- Mass blocks shall be in accordance with Keppel Block
- Placement of backfill to reinforced slope shall be in accordance with MRTS04.
- Placement of soil reinforcement and compaction of reinforced fill material to be in accordance with MRTS100
- Compliance testing of backfill material to be used for reinforced earth block to be in accordance with MRTS100. The minimum angle of internal friction is to be 30°.
- The following inspections will be required to be carried out by the Administrator during construction:
  - HOLD POINT – prior to commencement of works on the reinforced slope the Contractor shall supply a Work Method Statement for the installation of the soil reinforcement and compaction, including plant to be used. This will require approval prior to the commencement of works.
  - HOLD POINT – for approval of foundation, testing will be as follows:
    - DCP's at 5 m centres along the base excavation level
    - Proof roll full length of footing if practical
    - Witness inspection and approval of testing results by the Administrator.
    - Review retaining wall geometry at 10 m centres.
- Witness inspection for placing of blocks including the connection of the reinforcing grid and placement of fill levels.
- Placement of the fill in the reinforced block shall be Level 1 controlled fill as defined in AS3798-2007.
- Stability of the temporary cut and requirements of temporary slope support measures to be assessed by the Contractor.

**DRAINAGE**

- Existing road drainage pit invert level and location of 300 mm RCP outlet to be confirmed prior to commencement of works HOLD POINT.
- Field inlet pit to be in accordance with TMR Std Drg 1310, apron levels to tie into concrete lined drain.
- Drainage outlets to be provided within the concrete batter protection at locations as shown on the drainage plan. 100 dia PVC at 3 m centres and fitted with a flap valve.
- Access chamber shall be in accordance with TMR Std Drg 1307 unless noted otherwise.
- All pipes and culverts shall have a 50 year design life. The exposure classification for RCP shall be normal.
- All concrete pipes shall be installed with type HS3 support for concrete pipes in accordance with TMR Std Drg 1359 as appropriate unless noted otherwise.
- All stormwater pipes shall be minimum Class 3 RCP or approved equivalent unless noted otherwise. All pipes to be flush or butt joint types unless noted otherwise.
- Pipe class shown on the drawings allow the following mandatory minimum construction load cases in accordance with MRTS25.
  - Truck and dog trailer with minimum height of compacted fill of 0.5 m over the top of the pipe. Load is defined in MRTS25 Figure 5.7.1(a).
  - 25.9 tonne excavation and 580 mm compaction wheel acting separately with a minimum height of compacted fill of 1.0 m over the top of the pipe. Load is defined in MRTS25 Figure 5.7.1(b).
- The Contractor shall ensure construction loads on pipes and culverts shall not exceed those identified in MRTS25.
- Pipes shall be connected to pits such that the pipe is centred on the pit face unless otherwise noted.
- Existing stormwater pipe to be removed unless noted otherwise.

**ROCK PROTECTION**

- Rockfill protection to batters (riprap) shall comply with the requirements of MRTS03 with a D50 of 500 mm u.n.o.
- The geotextile separation layer shall be in accordance with TMR Standard drawing 2242 for heavy duty non-woven geotextile.

**FENCING**

- Pedestrian fencing shall be in accordance with Webforge Monowills to match the existing fencing.


**CONCRETE BATTER PROTECTION**

- All concrete exposure classification shall be B2.
- Concrete batters shall be in accordance with MRTS03.
- Concrete batter protection shall be S32/20/80.
- Concrete batter expansion joints at 8.0 m centres, perpendicular to the wall centre line unless noted otherwise.

**ABBREVIATIONS**

- Abbreviations used are in accordance with AS1100.101 1992 and TMR 'Drafting and Design Presentation Standard Manual'.
- Additional abbreviations used throughout the set are as follows:
  - AHD – Australian Height Datum
  - CIP – Cast in place
  - CJ – Construction Joint
  - CRS – Centres
  - DN – Nominal Diameter
  - DWS – Deck wearing surface
  - EGL – Approximate existing ground level
  - EJ – Expansion Joint
  - FSL – Finished surface level
  - HG – Hot dip galvanised
  - Ht – Height or reduced levels to Australian Height Datum
  - MRTS – Queensland Government Department of Transport and Main Roads Technical Standard
  - MRS – Queensland Government Department of Transport and Main Roads Standard Drawing
  - OAE – Or approved equivalent
  - R – Radius
  - RC – Reinforced Concrete
  - SOP – Setout Point
  - SS – Stainless Steel
  - TMR – Queensland Government Department of Transport and Main Roads
  - TYP – Typical
  - UG – Underground
  - UNO – Unless Noted Otherwise
  - VC – Vertical Curve

**SURVEY AND GENERAL ARRANGEMENT LEGEND**



Last Modified: 11 Jul 30, 2024 - 1:41PM

Associated Job Nos		Survey Data		Scales	228 FRASER COAST REGIONAL COUNCIL					DMTR EVENT 22A																	
		GDA2020			163 LAMINGTON BRIDGE – GYMPIE ROAD					GENERAL NOTES AND LEGEND																	
Auxiliary Drg Nos		MGA 56		NTS	CTL CHGE 2824 – 2905					SHEET 1																	
		AHD			Reference Points					ENGINEERING CERTIFICATION (RPEQ)																	
Revisions/Descriptions		Signatory: – RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title		Date		Survey Books		Dimensions shown in millimeters except where shown otherwise		Preceding RP		Dist. to start of job (km)		From start to end of job		From end to Following RP		Following RP		ENG. AREA		SIGNATORY FULL NAME		No.		DATE	
1 50% Design Review		17.05.2024				200418 001 200418				PSM 44312		0.07		0.08		0.18		PSM 15677		CIVIL		GEMMA THOMAS		32011		JULY 2024	
																				MATT HAMILTON		16194		JULY 2024			
																						Job No.		2835872			
																						Contract No.		CN-21784			
																						Drawing No.		953831 3			
																						Series Number		NL-01 of 03			







**CONCRETE NOTES**

- Concrete to be in accordance with MRTS70 Concrete.
- Exposure classification shall be B2 as per AS5100.5
- Concrete to be used in each element of the work shall be as follows:

ELEMENT	CLASS
Blinding Concrete	N20/20
Cast-in-place Piles	S40/20
Pile Caps	S40/20
Concrete foundation (Wall Type B)	S40/20

The class designation specifies the required Class and Grade to AS 1379-2007 and the nominal maximum aggregate size (mm).

- All exposed edges having a contained angle of less than 120° to have 20 x 20 chamfers unless shown otherwise.
- Construction joints shall be used only as shown on the drawings. No construction joint shown on the drawings shall be omitted without the written approval of the designer.

**REINFORCING STEEL NOTES**

- Reinforcing steel to be in accordance with AS/NZS 4671-2019 and MRTS71 Reinforcing Steel.
- Deformed bars Grade D500N.
- All carbon reinforcing steel to be Australasian Certification Authority for Reinforcing and Structural Steels ACRS certified.
- Reinforcing steel bar shapes shall be as detailed on MRSD 1043. Standard reinforcement abbreviations used on these drawings:
 

ABR	-	Alternate Bar Reversed	LV	-	Length Varies
ADD	-	Additional	NF	-	Near Face
ALT	-	Alternative	NSOE	-	Not shown on Elevation
B	-	Bottom face	NSOP	-	Not shown on plan
EF	-	Each face	T	-	Top face
ES	-	Equally spaced	STAG	-	Staggered
FF	-	Far face	EW	-	Each way
BW	-	Both ways	T&B	-	Top and Bottom
- A bar designated on the drawings as 8-16A5 at 300 means 8 of, 16 dia, A shape, bar number 5 in the schedule, Grade D500N and spaced at 300 centres.
- Minimum cover to reinforcing steel in each element shall be as follows:

ELEMENT	COVER
Cast-in-place Piles	65
Pile Caps	45

- Spacing of stirrups in pile caps may be altered slightly, if necessary, to clear pile starter bars.
- Laps and other splices in reinforcing steel shall only be made at the positions shown on the drawings unless alternative or extra locations are approved in writing by the Administrator
- Minimum development and splice lengths to AS 5100.5-2017 are as follows:

Bar Size	N12	N16	N20	N24	N28	N32	N36	N40
Development Length	400	550	750	900	1100	1300	1500	1750
Splice Length	500	700	900	1100	1350	1600	1850	2150

Development and splice lengths are based on:

- Minimum 40 MPa concrete characteristic compressive strength
- Minimum clear distance of 40 mm between reinforcement bars (incl. at splice locations).
- Maximum number of bars in a bundle: 2

The calculated lap lengths include a 1.25 factor in accordance with AS5100.5 C13.2.2. For horizontal bars with more than 300 mm of concrete cast below the bar the splice lengths shall be 1.3 times the values shown in the above table.

- Reinforcement is shown diagrammatically on these drawings and therefore does not depict the precise positions of bars.
- Welding of any reinforcement steel bars is NOT permitted.

**DESIGN NOTES**

- Retaining walls designed in accordance with:-
  - AS 5100-2017; AS 4678-2002.
  - Queensland Department of Transport and Main Roads – Structures: Design Criteria For Bridges and Other Structures Dated Feb. 2024.
  - Queensland Department of Transport and Main Roads – Geotechnical Design Standard – Minimum Requirements Dated Dec 2020.

**DESIGN LOADS**

- Concrete unit weight: 24 kN/m<sup>3</sup> (in-situ) including steel reinforcement
- Earth pressure: Unit weight of soil = 18 kN/m<sup>3</sup> Soil internal friction angle = 30°
- Live load surcharge: 5 kPa
- Unfactored structural design loads corresponding to the critical cross section and groundwater conditions are shown in the table below.

Design Case	Max. Bending Moment (kNm)	Max. Shear Force (kN)	Max. Axial load (kN)
Unfactored (RDD)	-125	60	-175

- Factored loads are shown in the table below

TOP OF PILES ULS DESIGN LOADS			
Design Case	Design Resultant Axial Compression (kN)	Design Resultant Moment (kN)	Design Resultant Shear (kN)
Factored	263	221	90

**DIMENSION/HEIGHT NOTES**

- Heights, Chainages and Co-ordinates are all in metres unless noted otherwise on the design drawings.
- All other dimensions are in millimetres, UNO.
- All Heights are to Australian Height Datum.
- All co-ordinates are to GDA20.
- Dimensions shall not be scaled from drawings.

**SECANT PILE WALL (WALL TYPE 2A)**

- All necessary construction methods and steps shall be used to maintain the integrity of the primary piles during drilling and installation of the secondary piles.
- The reinforcing steel grade is D500 which is hot rolled deformed bars with a Yield Stress of 500 MPa
- The minimum lap lengths shall comply with AS3600 section 13.1
- The setting out and verticality of all piles shall be well controlled to ensure a minimum overlapping of 25 mm at any depth.
- All concrete works shall comply with AS 3600 and piling in accordance with AS2159;
  - Concrete Characteristic Strength F<sub>c</sub> to be 25 MPa for the primary piles and 40 MPa for the secondary piles.
  - For secondary piles which are the only piles to have reinforcing steel the concrete cover is 75 mm.
  - The Contractor shall only constructs the secondary piles once the primary piles have attained and F<sub>c</sub> of 20 MPa minimum, or an age at which the constructor considers it is acceptable to drill secondary piles without compromising the structural integrity or verticality requirements.
  - Design Exposure condition is moderate in accordance with AS2159-2009.



Last Modified: 1 Jul 30, 2024 - 1:45PM

		Associated Job Nos	Survey Data		Scales	228 FRASER COAST REGIONAL COUNCIL				DMTR EVENT 22A				Queensland Government		
			Horiz. Datum	GDA2020		163 LAMINGTON BRIDGE – GYMPIE ROAD				GENERAL NOTES AND LEGEND						
		Auxiliary Drg Nos	Horiz. Grid	MGA 56	NTS	CTL CHGE 2824 – 2905				STRUCTURAL NOTES						
			Height Datum	AHD		Reference Points				ENGINEERING CERTIFICATION (RPEQ)						
2	100% Design Issue					Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP	ENG. AREA	SIGNATORY FULL NAME	No.	DATE	Job No.	2835872
1	85% Design Review					PSM 44312	0.07	0.08	0.18	PSM 15677	CIVIL	GEMMA THOMAS	32011	JULY 2024	Contract No.	CN-21784
Revisions/Descriptions		Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title	Date			Dimensions shown in millimeters except where shown otherwise					MATT HAMILTON	16194	JULY 2024	Drawing No.	953832	2
CAD FILES		AECOM_DS13_AU\Documents\60701625-TMR WBB REPA\900_CAD_GIS\910_CAD\20_Sheets\Civil\60701625-ACM-3001-910-300-DRG-03002-NL				Through Chainage from								Series Number	NL-02	of 03



CONSTRUCTION NOTES

1. An adequate site surface must be provided as a safe working platform for piling equipment.
2. Piles must be constructed in accordance with the installation procedure for non-displacement piles in AS 2159 and MRTS63A.
3. The Contractor shall confirm the use in piling of temporary construction liners for this project.
4. Piles shall be installed using appropriate boring and installation equipment capable of producing the required outcome. All necessary installation equipment shall be available on site prior to commencement of piling.
5. The Contractor's attention is drawn to the varied nature of the foundation material as indicated by the borehole log geotechnical report and the potential to intersect ground water during the installation of the piles.
6. Where relevant, the methods of transport, handling and storage of materials and equipment shall be such as to prevent any damage to the steel pile casings, such as the result of impact, deflection or the application of load.
7. All piles shall be set out in accordance with design requirements and appropriate procedures shall be taken to protect adjacent services, structures, and piles.
8. Check the horizontal position and verticality/batter angle of the piling / drilling rig prior to the construction of each pile.
9. The piling Contractor shall sequence the works in such a way as to provide sufficient distance between piles to ensure that adjacent piles are not damaged during drilling and construction of subsequent piles.
10. Locate construction equipment at sufficient distance from the pile being drilled and from recently constructed piles to avoid any displacement of the concrete column caused by the load of the equipment.
11. Confirm set out of all piles before commencing installation.

BORING AND EXCAVATION NOTES

1. The piling rig must be capable of installing piles to the depth and to alignment within the secant drilling operations, all as shown on the approved drawings with provision for contingencies.
2. Boring and excavation shall be such as to keep over-break to a minimum.
3. The side of all boreholes shall be kept intact and no loose material shall be permitted to fall into the bottom of the boreholes.
4. The borehole may be filled with drilling fluid to a level to sufficiently stabilise the borehole. If drilling fluid alone is not sufficient to prevent the ground water from intrusion or the borehole side walls from collapse, a steel casing of appropriate size and length shall be used in conjunction with the drilling fluid to support the side of the borehole.
5. If a temporary casing is required to stabilise the borehole, it shall be extended beyond the unstable strata for one meter or more to prevent the inflow of soil and the formation of cavities in the surrounding ground.
6. If a temporary casing is damaged during installation in a manner which prevents the proper formation of the pile, such a casing shall be withdrawn from the borehole and repaired if necessary, or other measure to be taken to the approval of the Principal or the delegated authority to continue the construction of the pile.
7. The pile toe shall be founded at the levels shown on the Drawings and shall be witnessed by the administrator.
8. During the installation process, if the ground condition varies from that assumed at design stage or as shown in borehole logs completed during geotechnical investigation, the Designer or the delegated authority shall determine the need for further deepening of the pile shaft.
9. The Administrator's Geotechnical Assessor shall decide when the founding level is satisfactory, and the pile shaft can be prepared for concreting.

CONCRETING

1. Concrete works shall comply with the requirements of MRTS70.
2. Placing and compaction of concrete shall be in accordance with the MRTS70.
3. Concreting must be continuous to achieve monolith from the top to the base of the pile, without segregation and free of entrapped debris.
4. Concreting shall be continued to 300 mm above the designed pile cut off level to ensure any contaminated concrete is removed. A temporary casing may be required to achieve the concreting level.
5. Any ground water must be displaced during concreting operations.
6. The volume of concrete used in the pile shall be determined to an accuracy of 5% and recorded. The measured volume of concrete placed in any pile shall be not less than 105% of the nominal volume of the pile.
7. If the recorded volume of the concrete placed in the borehole indicates a possible necking, the Piling Contractor shall propose and carry out appropriate tests and measures to demonstrate the adequacy of the pile, or appropriate remedy work to the approval of the Designer or delegated authority.

CASING EXTRACTION

1. Notwithstanding other clauses within this section casing extraction shall comply with the requirements of MRTS63A.
2. Withdraw of any temporary casing shall be carried out whilst the concrete still fluid and has a slump close to that while concreting so that no concrete is lifted.
3. If temporary liners are utilised, full details of their removal shall be provided. Any space between pile and ground shall be completely backfilled using flowable fill or other approved material.

CLEANING AND INSPECTION OF BOREHOLE

1. All pile construction works shall be carried out in accordance with MRTS63A. The Contractor shall submit written procedures for all construction processes and testing for review prior to commencement. The Lot Size for testing shall be 100% for integrity testing & 1 in 3 of secondary piles for load testing.
2. The tops of piles shall be constructed to elevations indicated on the design drawings prior to construction of the pile capping beam. All contaminated and weak concrete and laitance must be removed to expose sound concrete over the full cross sectional area of the pile prior to capping beam construction commencement.
3. Pile construction and verification to conform with the requirements of MRTS63A piles for ancillary structures.
4. Upon completion of boring, the pile holes shall be cleaned of all loose, disturbed soil and sediment soil to expose a sound base of undisturbed material using a suitable and effective method to be approved by the Designer or the delegated authority.
5. Where practicable, (and where temporary liners are not used) all boreholes shall be inspected for their full length prior to concreting to ensure the cleaning has been properly carried out; the sides are able to remain stable during subsequent installation of reinforcement cage and concreting operations; and the verticality and position of the boreholes meet the specified tolerances.
6. The Piling Contractor shall provide all necessary apparatus for the inspection to be carried out safely.
7. The construction of cast-in-place piles shall be logged, inspected and certified by Geotechnical Assessor (GA) in accordance with MRTS63A.

PLACEMENT OF REINFORCEMENT

1. Reinforcement shall comply with MRTS71.
2. The reinforcement cage shall be free from oil, rust or debris and straight. It shall not be placed until inspected and accepted by the Administrator.
3. Reinforcement must be carefully aligned as shown on the drawings to allow the satisfactory construction of the pile caps.
4. Spacer skids with contact width of not less than 35mm must be used for the installation of reinforcement to ensure maintenance of cover requirements as specified on the drawings. Not less than 4 spacer skids shall be provided evenly around the perimeter of the pile at a vertical spacing of not less than 2 meters.
5. Reinforcement cages and spacers shall be sufficiently robust to withstand the forces during lifting, placing of the concrete and extraction of temporary casings.
6. The cage shall be kept vertical or at the required batter angle (if applicable) during installation.
7. Welding of reinforcing bars is NOT permitted and any reinforcing steel that has been welded shall be replaced.
8. If the reinforcement cage cannot be placed to the specified depth, the cage must be removed and the pile re-drilled.

TOLERANCE ON PILES

1. Tolerance on piles shall be in accordance with MRTS63 to be confirmed based on constructability for the pile length.
2. The pile diameter shall not be less than shown on the drawings. The pile diameter may generally be larger than shown on the drawings, providing that the minimum distance from the outside of any pile to the edge of a concrete pile cap/pier/abutment as shown on the drawings is satisfied after taking into account construction tolerances.

Last Modified: 17 Jul 30, 2024 - 1:42PM

Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or - Full Name and Position Title	Date
3 100% Design Issue		19.07.2024
2 85% Design Review		07.06.2024
1 50% Design Review		17.05.2024

Associated Job Nos	Survey Data	Scales
	Horiz. Datum GDA2020	NTS
Auxiliary Drg Nos	Horiz. Grid MGA 56	
	Height Datum AHD	
	Survey Books 200418 001 200418	


228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677
Through Chainage from				

DMTR EVENT 22A GENERAL NOTES AND LEGEND SHEET 3			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024



Queensland Government	
Job No.	2835872
Contract No.	CN-21784
Drawing No.	953833 3
Series Number	NL-03 of 03





KEPPEL BLOCK REINFORCED SLOPE TYPICAL SECTION

NOTES

- 1. Refer to drawings 935831 to 935833 for general notes



Last Modified: 1 Jul 30, 2024 - 1:42PM

Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or - Full Name and Position Title	Date
4 100% Design Issue		19.07.2024
3 85% Design Review		07.06.2024
2 50% Design Review		17.05.2024
1 30% Design Review		04.03.2024

Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
	Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418


Scales

Dimensions shown in millimeters except where shown otherwise

228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677
Through Chainage from				

DMTR EVENT 22A TYPICAL SECTION SHEET 1			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024

Queensland Government	
Job No.	2835872
Contract No.	CN-21784
Drawing No.	953834 4
Series Number	TC-01 of 02



**REINFORCED CONCRETE SPILLTHROUGH PROTECTION**  
SCLAE 1:25

**NOTES**


1. Construction of abutment protection shall be in accordance with MRTS03 and read in conjunction with TMR Standard Drawing 2235.
2. Concrete shall be in accordance with MRTS70. Design life 50 years.
3. Reinforcing steel shall be read in conjunction with TMR Standard Drawing 1044, shall be in accordance with MRTS71 and to AS/NZS 4671, and ACRS certified.
4. Special care shall be taken as to not disturb or damage the existing heritage timber piles and formwork.
5. Contractor to document and record locations of heritage items prior to placement of concrete batter protection.
6. Sand backfill shall be placed and compacted around the heritage listed items identified to be protected.

**APPROVED**

Name: Trudi Smith  
Date: 12:42 pm, 21/10/2024


Last Modified: 11 Jul 30, 2024 - 1:45PM

Associated Job Nos		Survey Data		Scales 0 500 1000mm Dimensions shown in millimeters except where shown otherwise	228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905					DMTR EVENT 22A TYPICAL SECTION SHEET 2				Queensland Government	
Auxiliary Drg Nos		Horiz. Datum			Reference Points					ENGINEERING CERTIFICATION (RPEQ)				Job No. 2835872	
		GDA2020			Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP	ENG. AREA	SIGNATORY FULL NAME	No.	DATE	Contract No. CN-21784	
		MGA 56		PSM 44312	0.07	0.08	0.18	PSM 15677	CIVIL	GEMMA THOMAS	32011	JULY 2024	Drawing No. 953835 4		
		AHD		Through Chainage from					MATT HAMILTON				Series Number TC-02 of 02		
Survey Books		200418 001 200418													
Revisions/Descriptions		Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or - Full Name and Position Title		Date											
1 30% Design Review				04.03.2024											
2 50% Design Review				17.05.2024											
3 85% Design Review				07.06.2024											
4 100% Design Issue				19.07.2024											




NOTE  
Wall foundation omitted for clarity


**BATTER CHUTE DETAIL**  
SCALE 1:25



**SECTION A-A**  
SCALE 1:25



**SECTION B-B**  
SCALE 1:25



**SECTION C-C**  
SCALE 1:25

- NOTES:**
1. Refer to drawings 935831 to 935833 for general notes.
  2. Refer to drawing 935831 for drainage details.


**APPROVED**

Name: Trudi Smith  
Date: 12:42 pm, 21/10/2024


Last Modified: 21 Jul 30, 2024 - 1:42PM

Associated Job Nos		Survey Data		Scales 0 0.1 0.2 0.3 0.4m Dimensions shown in millimeters except where shown otherwise	228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905					DMTR EVENT 22A GENERAL DETAILS SHEET 1				Job No. 2835872	
Auxiliary Drg Nos		Horiz. Datum	GDA2020		Reference Points					ENGINEERING CERTIFICATION (RPEQ)				Contract No. CN-21784	
		Horiz. Grid	MGA 56		Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP	ENG. AREA	SIGNATORY FULL NAME	No.	DATE	Drawing No. 953836 3	
Revisions/Descriptions		Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title	Date	Survey Books	PSM 44312	0.07	0.08	0.18	PSM 15677	CIVIL	MATT HAMILTON	16194	JULY 2024	Series Number GD-01 of 02	


Job No. 2835872  
Contract No. CN-21784  
Drawing No. 953836 3  
Series Number GD-01 of 02




**PLAN – CONCRETE BATTER PROTECTION TIE IN WITH KEPPEL BLOCK**  
SCALE 1:15



**DETAIL B – SEALANT DETAIL**  
SCALE NTS




**KEYED CONSTRUCTION JOINT (KJ)**  
SCALE NTS




**LONGITUDINAL ELEVATION – KEPPEL BLOCK**  
SCALE 1:15


Block surface to be cleared of any protrusions and debris prior to the placement of 2 layers of 300 um Visqueen



**SECTION A-A**  
SCALE 1:15



**CONCRETE BATTER PROTECTION**  
SCALE 1:15



**KEPPEL BLOCK WALL DRAINAGE OUTLET**  
SCALE 1:15

Last Modified: 21 Jul 30, 2024 - 1:42PM


Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or - Full Name and Position Title	Date
3 100% Design Issue		19.07.2024
2 85% Design Review		07.06.2024
1 50% Design Review		17.05.2024

Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
	Auxiliary Drg Nos: Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418


228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE – GYMPIE ROAD CTL CHGE 2824 – 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677
Through Chainage from				

DMTR EVENT 22A GENERAL DETAILS SHEET 2			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024


Job No.	2835872
Contract No.	CN-21784
Drawing No.	953837 3
Series Number	GD-02 of 02




PLAN - WALL 1A PILE CAP  
SCALE A




TYPICAL CROSS SECTION - TYPE 1A WALL  
SCALE A




LONGITUDINAL ELEVATION - PILE  
SCALE A



LONGITUDINAL ELEVATION - PILE CAP  
SCALE A



SECTION SCALE A



SECTION SCALE A



NOTES


1. Refer to drawings 935831 to 935833 for General notes
2. Refer to drawing 935831 for Drainage details
3. Refer to drawing 935841 for Pile schedule
4. Concrete shall be placed in one operation between construction joints.

Last Modified: 11 Jul 30, 2024 - 1:42PM


<table border="1"> <tr> <th>Revisions/Descriptions</th> <th>Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title</th> <th>Date</th> </tr> <tr> <td>4</td> <td>100% Design Issue</td> <td>19.07.2024</td> </tr> <tr> <td>3</td> <td>85% Design Review</td> <td>07.06.2024</td> </tr> <tr> <td>2</td> <td>50% Design Review</td> <td>17.05.2024</td> </tr> <tr> <td>1</td> <td>30% Design Review</td> <td>04.03.2024</td> </tr> </table>			Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title	Date	4	100% Design Issue	19.07.2024	3	85% Design Review	07.06.2024	2	50% Design Review	17.05.2024	1	30% Design Review	04.03.2024	<table border="1"> <tr> <th>Associated Job Nos</th> <th>Survey Data</th> </tr> <tr> <td></td> <td>Horiz. Datum: GDA2020</td> </tr> <tr> <th>Auxiliary Drg Nos</th> <td>Horiz. Grid: MGA 56</td> </tr> <tr> <td></td> <td>Height Datum: AHD</td> </tr> <tr> <td></td> <td>Survey Books: 200418 001, 200418</td> </tr> </table>		Associated Job Nos	Survey Data		Horiz. Datum: GDA2020	Auxiliary Drg Nos	Horiz. Grid: MGA 56		Height Datum: AHD		Survey Books: 200418 001, 200418	<p>Scales</p> <p>0 150 300 450 600mm</p> <p>Dimensions shown in millimeters except where shown otherwise</p>		<p>228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905</p> <table border="1"> <tr> <th colspan="5">Reference Points</th> </tr> <tr> <th>Preceding RP</th> <th>Dist. to start of job (km)</th> <th>From start to end of job</th> <th>From end to Following RP</th> <th>Following RP</th> </tr> <tr> <td>PSM 44312</td> <td>0.07</td> <td>0.08</td> <td>0.18</td> <td>PSM 15677</td> </tr> </table> <p>Through Chainage from</p>				Reference Points					Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP	PSM 44312	0.07	0.08	0.18	PSM 15677	<p>DMTR EVENT 22A STRUCTURAL DETAILS - WALL 1A SHEET 1</p> <table border="1"> <tr> <th colspan="4">ENGINEERING CERTIFICATION (RPEQ)</th> </tr> <tr> <th>ENG. AREA</th> <th>SIGNATORY FULL NAME</th> <th>No.</th> <th>DATE</th> </tr> <tr> <td>GEOTECH</td> <td>GEMMA THOMAS</td> <td>32011</td> <td>JULY 2024</td> </tr> <tr> <td>CIVIL</td> <td>MATT HAMILTON</td> <td>16194</td> <td>JULY 2024</td> </tr> </table>				ENGINEERING CERTIFICATION (RPEQ)				ENG. AREA	SIGNATORY FULL NAME	No.	DATE	GEOTECH	GEMMA THOMAS	32011	JULY 2024	CIVIL	MATT HAMILTON	16194	JULY 2024	<p>Job No. 2835872</p> <p>Contract No. CN-21784</p> <p>Drawing No. 953838 4</p> <p>Series Number SD-01 of 03</p>	
Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title	Date																																																																						
4	100% Design Issue	19.07.2024																																																																						
3	85% Design Review	07.06.2024																																																																						
2	50% Design Review	17.05.2024																																																																						
1	30% Design Review	04.03.2024																																																																						
Associated Job Nos	Survey Data																																																																							
	Horiz. Datum: GDA2020																																																																							
Auxiliary Drg Nos	Horiz. Grid: MGA 56																																																																							
	Height Datum: AHD																																																																							
	Survey Books: 200418 001, 200418																																																																							
Reference Points																																																																								
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP																																																																				
PSM 44312	0.07	0.08	0.18	PSM 15677																																																																				
ENGINEERING CERTIFICATION (RPEQ)																																																																								
ENG. AREA	SIGNATORY FULL NAME	No.	DATE																																																																					
GEOTECH	GEMMA THOMAS	32011	JULY 2024																																																																					
CIVIL	MATT HAMILTON	16194	JULY 2024																																																																					









**CONSTRUCTION JOINT**  
Scale B




**CAPPING BEAM**  
SCALE B




**LONGITUDINAL ELEVATION - WALL 2A SECONDARY PILE**  
SCALE B




**CONSTRUCTION JOINT**  
SCALE B



**WALL 2A SECANT PILE ARRANGEMENT**  
SCALE B



**SECONDARY PILE CROSS SECTION**  
Scale B



**DETAIL A**  
SCALE B



Last Modified: Jul 30, 2024 - 1:42PM

3	100% Design Issue	19.07.2024
2	85% Design Review	07.06.2024
1	50% Design Review	17.05.2024
Revisions/Descriptions		Date
Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title		Date


Associated Job Nos	Survey Data
Auxiliary Drg Nos	Horiz. Datum: GDA2020
	Horiz. Grid: MGA 56
	Height Datum: AHD
Survey Books	200418 001 200418

228 FRASER COAST REGIONAL COUNCIL				
163 LAMINGTON BRIDGE - GYMPIE ROAD				
CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677
Through Chainage from				


DMTR EVENT 22A			
STRUCTURAL DETAILS - WALL 1B			
SHEET 3			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024

Job No.	2835872
Contract No.	CN-21784
Drawing No.	953840 3
Series Number	SD-03 of 03





01 PLAN  
Scale A



WALL TYPE 1A		21.7	
WALL HEIGHT	1.468	1.468	1.468
UPPER LEVEL (B)	3.848	3.853	3.873
LOWER LEVEL (A)	2.380	2.385	2.405
BOTTOM OF CAPPING BEAM	1.880	1.925	1.950
TOP OF PILE	1.950	1.975	2.000
EXISTING LEVELS	1.044	0.961	1.335
DISTANCE	0.000	1.059	5.000

WALL ELEVATION -> MW300101  
Scale A

PILE No	CHAINAGE	EASTING	NORTHING	TOP OF PILE (RL)	PILE LENGTH (m)#
P19	0.45	468511.893	7174655.816	5.404	13.104
P20	0.95	468511.393	7174655.821	5.446	13.146
P21	1.45	468510.894	7174655.789	5.486	13.186
P22	1.95	468510.398	7174655.722	5.528	13.228
P23	2.45	468509.909	7174655.621	5.569	13.269
P24	2.95	468509.428	7174655.484	5.608	13.308
P25	3.45	468508.958	7174655.313	5.647	13.347
P26	3.95	468508.501	7174655.110	5.686	13.386
P27	4.45	468508.060	7174654.874	5.727	13.427
P28	4.95	468507.637	7174654.608	5.769	13.469
P29	5.45	468507.234	7174654.311	5.809	13.509
P30	5.95	468506.853	7174653.987	5.850	13.550
P31	6.45	468506.496	7174653.637	5.891	13.591

NOTES:  
# - Piles shall be extended to RL-7.7 m AHD as a minimum in addition to meeting the embedment requirements.



PILE No	CHAINAGE	EASTING	NORTHING	TOP OF PILE (RL)	PILE LENGTH (m)#
P1	0.72	468532.379	7174655.617	1.954	12.95
P2	1.92	468531.432	7174656.353	1.960	12.96
P3	3.12	468530.376	7174656.924	1.966	12.97
P4	4.32	468529.238	7174657.306	1.973	12.97
P5	5.52	468528.054	7174657.499	1.979	12.98
P6	6.72	468526.863	7174657.645	1.985	12.99
P7	7.92	468525.672	7174657.792	1.991	12.99
P8	9.12	468524.481	7174657.938	1.997	12.70
P9	10.32	468523.290	7174658.084	2.003	12.26
P10	11.52	468522.099	7174658.230	2.009	11.83
P11	12.72	468520.908	7174658.376	2.015	11.40
P12	13.92	468519.717	7174658.523	2.021	10.96
P13	15.12	468518.526	7174658.669	2.027	10.53
P14	16.32	468517.335	7174658.815	2.033	10.09
P15	17.52	468516.136	7174658.881	2.039	9.739
P16	18.72	468514.947	7174658.723	2.046	9.745
P17	19.92	468513.809	7174658.341	2.053	9.751
P18	21.12	468512.764	7174657.751	2.059	9.757

NOTES:  
# - Piles shall be extended to RL-7.7 m AHD as a minimum in addition to meeting the embedment requirements.

- NOTES:
1. Refer to drawings 931831 to 931833 for general notes.
  2. Refer Geotechnical Design report and Geotechnical investigation report for the details of inferred embedment layer

Last Modified: 1 Jul 30, 2024 - 1:42PM

Associated Job Nos Survey Data Horiz. Datum: GDA2020 Auxiliary Drg Nos Horiz. Grid: MGA 56 Height Datum: AHD Survey Books: 200418 001, 200418		Scales Scale A: 0 1 2 3 4m Scale B: 0 0.1 0.2 0.3 0.4m Dimensions shown in metres except where shown otherwise		228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905				DMTR EVENT 22A PILE ELEVATION CONTROL LINE MW300101				Job No. 2835872	
Revisions/Descriptions Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title Date		Preceding RP: PSM 44312 Dist. to start of job (km): 0.07 From start to end of job: 0.08 From end to Following RP: 0.18 Following RP: PSM 15677 Through Chainage from		ENGINEERING CERTIFICATION (RPEQ) SIGNATORY FULL NAME No. DATE GEMMA THOMAS 32011 JULY 2024 MATT HAMILTON 16194 JULY 2024		Contract No. CN-21784 Drawing No. 953841 3 Series Number MD-01 of 01							



MODEL : CONTROL 3001 RDW WALL - STRING : MW300101

PT	CHAINAGE	EASTING	NORTHING	HEIGHT	BEARING	DEP.SEG	DEP.RAD	DEP.LEN
Start	0.000	468533.247	7174655.527	2.380	310°21'14.33"	LINE		
TC	1.059	468532.440	7174656.213	2.385	310°21'14.33"	ARC	-7.500	4.366
	5.000	468528.918	7174657.877	2.405	280°14'50.74"		-7.500	
CT	5.425	468528.498	7174657.941	2.407	277°00'00.00"	LINE		11.381
	10.000	468523.957	7174658.499	2.430	277°00'00.00"			
	15.000	468518.995	7174659.108	2.455	277°00'00.00"			
TC	16.806	468517.202	7174659.328	2.464	277°00'00.00"	ARC	-6.800	5.610
	20.000	468514.057	7174658.972	2.480	250°05'15.80"		-6.800	
End	22.416	468511.978	7174657.767	2.492	229°43'51.61"			

MODEL : CONTROL 3001 RDW SPILLTHROUGH - STRING : MW300102

PT	CHAINAGE	EASTING	NORTHING	HEIGHT	BEARING	DEP.SEG	DEP.RAD	DEP.LEN
Start	0.000	468539.930	7174641.706	5.419	38°57'50.98"	LINE		
Point	2.102	468541.251	7174643.341	4.770	38°57'47.70"	LINE		3.311
	5.000	468543.074	7174645.594	3.230	38°57'47.70"			
TC	5.413	468543.334	7174645.915	2.817	38°57'47.70"	ARC	-0.100	0.155
CT	5.568	468543.321	7174646.054	2.662	310°19'04.68"	LINE		6.136
	10.000	468539.941	7174648.922	2.662	310°19'04.68"			
Point	11.704	468538.642	7174650.025	2.662	310°21'14.33"	LINE		7.674
	15.000	468536.130	7174652.159	2.662	310°21'14.33"			
TC	19.378	468532.794	7174654.993	2.662	310°21'14.33"	ARC	-0.100	0.158
CT	19.536	468532.653	7174654.981	2.679	219°48'34.63"	LINE		1.712
	20.000	468532.355	7174654.625	3.019	219°48'34.63"			
End	21.248	468531.557	7174653.666	3.934	219°48'34.63"			

INSTRUMENT STATION SURVEY MARKS

PointNumber	XCoord	YCoord	ZCoord	VertexText
1	468480.826	7174561.682	11.397	ROSTN100 SIC
2	468541.577	7174644.857	5.658	ROSTN101 SIC
3	468580.748	7174613.652	2.812	FSSTN102
4	468502.158	7174643.736	8.393	ROSTN103 SPK
5	468465.107	7174586.628	11.184	FSSTN104 SKP

PERMANENT STATION SURVEY MARKS

XCoord	YCoord	ZCoord	VertexText
468653.016	7174799.084	106.058	PSM No 15677
468443.285	7174538.930	112.911	PSM No 44312

MODEL : CONTROL 3001 RDW WALL - STRING : MW300103

PT	CHAINAGE	EASTING	NORTHING	HEIGHT	BEARING	DEP.SEG	DEP.LEN
Start	0.000	468528.919	7174654.270	4.317	304°01'43.72"	ARC	
CT	3.800	468525.376	7174655.526	4.336	275°00'00.00"	LINE	13.156
	5.000	468524.180	7174655.631	4.342	275°00'00.00"		
	10.000	468519.199	7174656.067	4.367	275°00'00.00"		
	15.000	468514.218	7174656.502	4.392	275°00'00.00"		
End	16.955	468512.270	7174656.673	4.402	275°00'00.00"		

MODEL : CONTROL 3001 RDW DRAINAGE - STRING : MD300101


PT	CHAINAGE	EASTING	NORTHING	HEIGHT	BEARING	DEP.SEG	DEP.RAD	DEP.LEN
Start	0.000	468526.273	7174652.261	5.623	305°33'05.48"	LINE		
TC	0.302	468526.027	7174652.436	5.625	305°33'05.48"	ARC	-5.000	2.666
End	2.968	468523.556	7174653.350	5.642	275°00'00.00"			



Last Modified: 21 Jul 30, 2024 - 1:42PM

2 100% Design Issue 1 85% Design Review	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title Date	Associated Job Nos	Survey Data	Scales 0 1 2 3 4m Dimensions shown in millimeters except where shown otherwise	<b>228 FRASER COAST REGIONAL COUNCIL</b> 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905	DMTR EVENT 22A CONTROL LINES LAYOUT AND SETOUT TABLES	Job No. 2835872 Contract No. CN-21784 Drawing No. 953842 2 Series Number CL-01 of 01																						
		Auxiliary Drg Nos	Horiz. Datum: GDA2020 Horiz. Grid: MGA 56 Height Datum: AHD		Reference Points	ENGINEERING CERTIFICATION (RPEQ)																							
		Survey Books	200418 001 200418		<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Preceding RP</th> <th>Dist. to start of job (km)</th> <th>From start to end of job</th> <th>From end to Following RP</th> <th>Following RP</th> </tr> </thead> <tbody> <tr> <td>PSM 44312</td> <td>0.07</td> <td>0.08</td> <td>0.18</td> <td>PSM 15677</td> </tr> </tbody> </table> Through Chainage from	Preceding RP		Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP	PSM 44312	0.07	0.08	0.18	PSM 15677	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>ENG. AREA</th> <th>SIGNATORY FULL NAME</th> <th>No.</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td>GEOTECH</td> <td>GEMMA THOMAS</td> <td>32011</td> <td>JULY 2024</td> </tr> <tr> <td>CIVIL</td> <td>MATT HAMILTON</td> <td>16194</td> <td>JULY 2024</td> </tr> </tbody> </table>	ENG. AREA	SIGNATORY FULL NAME	No.	DATE	GEOTECH	GEMMA THOMAS	32011	JULY 2024	CIVIL	MATT HAMILTON	16194	JULY 2024
		Preceding RP	Dist. to start of job (km)		From start to end of job	From end to Following RP		Following RP																					
PSM 44312	0.07	0.08	0.18	PSM 15677																									
ENG. AREA	SIGNATORY FULL NAME	No.	DATE																										
GEOTECH	GEMMA THOMAS	32011	JULY 2024																										
CIVIL	MATT HAMILTON	16194	JULY 2024																										
Revisions/Descriptions	Date																												





**LEGEND**

	Property Boundary		Existing Features
	Fence		Batter
	Control Line and Chainages		Existing Kerb
	Top of Batter		Existing Guardrail
	Existing Electricity O/H		Sign - Single
	Existing Gas U/G		Sign - Double
	Existing Telecomms U/G		Tree
	Existing Water Main		Drainage Flow Path
	Existing Sewer Rising Main		Fence
	Existing Stormwater		

Last Modified: 1 Jul 30, 2024 - 1:42PM

Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or - Full Name and Position Title	Date
3 100% Design Issue		19.07.2024
2 85% Design Review		07.06.2024
1 50% Design Review		17.05.2024

Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
Auxiliary Drg Nos	Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418


Scales  
 0 1 2 3 4 5m  
 Dimensions shown in metres except where shown otherwise

228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD				
<b>CTL CHGE 2824 - 2905</b>				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677
Through Chainage from				

DMTR EVENT 22A GENERAL ARRANGEMENT			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024

	<b>Queensland Government</b>
Job No.	2835872
Contract No.	CN-21784
Drawing No.	953843 3
Series Number	GA-01 of 01





DATUM -13							
UPPER LEVEL (B) -----	3.848	3.853	3.873 3.875	3.898	3.923	3.932	3.948
LOWER LEVEL (A) -----	2.380	2.385	2.405 2.407	2.430	2.455	2.464	2.480
EXISTING LEVELS -----	1.044	0.961	1.335 1.384	1.565	1.461	1.562	2.879
DISTANCE	0.000	1.059	5.000 5.425	10.000	15.000	16.806	20.000
							22.416


WALL ELEVATION -> MW300101



Last Modified: 1: Jul 30, 2024 - 1:42PM

Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or - Full Name and Position Title	Date
4 100% Design Issue		19.07.2024
3 85% Design Review		07.06.2024
2 50% Design Review		17.05.2024
1 30% Design Review		04.03.2024


Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
Auxiliary Drg Nos	Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418



228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677

DMTR EVENT 22A LONGITUDINAL SECTIONS CONTROL LINE MW300101			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024

Queensland Government	
Job No.	2835872
Contract No.	CN-21784
Drawing No.	953844 4
Series Number	LS-01 of 04




WALL ELEVATION -> MW300103



Last Modified: 19 Jul 30, 2024 - 1:45PM

4 100% Design Issue 3 85% Design Review 2 50% Design Review 1 30% Design Review		19.07.2024 07.06.2024 17.05.2024 04.03.2024	Associated Job Nos Survey Data Horiz. Datum: GDA2020 Auxiliary Drg Nos Horiz. Grid: MGA 56 Height Datum: AHD Survey Books: 200418 001, 200418	Scales 0 1 2 3 4m Dimensions shown in metres except where shown otherwise	228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905	DMTR EVENT 22A LONGITUDINAL SECTIONS CONTROL LINE MW300103	Queensland Government Job No. 2835872 Contract No. CN-21784 Drawing No. 953845 4 Series Number LS-02 of 04
Revisions/Descriptions Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title Date					Reference Points Preceding RP: PSM 44312, Dist. to start of job (km): 0.07 From start to end of job: 0.08 From end to Following RP: 0.18 Following RP: PSM 15677	ENGINEERING CERTIFICATION (RPEQ) ENG. AREA: GEOTECH, CIVIL SIGNATORY FULL NAME: GEMMA THOMAS, MATT HAMILTON No.: 32011, 16194 DATE: JULY 2024, JULY 2024	




- NOTES:**
1. Refer to drawings 953831 and 935832 for general notes
  2. Refer to drawing 953847 for drainage long section.
  3. Invert level of the existing pit is unknown and to be confirmed on site prior to commencement of works.
  4. Drainage outlet pipes to be fitted with flap valve.

Last Modified: 1 Jul 30, 2024 - 1:45PM

Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or - Full Name and Position Title	Date
2	100% Design Issue	19.07.2024
1	85% Design Review	07.06.2024

Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
	Auxiliary Drg Nos: Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418




228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677
Through Chainage from				

DMTR EVENT 22A DRAINAGE LAYOUT			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024

Job No.	2835872
Contract No.	CN-21784
Drawing No.	953846 2
Series Number	DD-LD-01 of 01



STRUCTURE NAME	1/100	2/100	3/100	4/100	5/100
STRUCTURE DESCRIPTION	EXISTING GRADE INLET ON GRADE - GRADE ONLY	1050mm DIA. ACCESS CHAMBER REFER TMR DWG 1307	FIELD INLET TYPE 2 - SINGLE GULLY REFER TMR DWG 1310	CAST-IN-SITU HEADWALL Refer to Drawing 953839 for Headwall detail	SHOTCRETE CHANNEL Refer to Drawing 953836 for details



PIPE SIZE (mm)	300	375	450	CHNL
PIPE TYPE (CLASS)	EX PIPE	RCP (4)	RCP (4)	
PIPE GRADE (%)	0.50%	6.08%	0.30%	10.82%
PIPE SLOPE (1 in X)	200.0	16.5	333.3	9.2
PIPE FLOW (cumecs) (10% AEP)	0.089	0.089	0.129	0.129
PIPE CAPACITY AT GRADE (cumecs)	0.068	0.432	0.156	3.303
FULL PIPE VELOCITY (m/s)	1.26	0.81	0.81	0.34
NORMAL DEPTH VELOCITY (m/s)	1.26	3.08	1.10	2.63
DATUM RL	-13.0			
HGL ELEVATION (10% AEP)	5.423 4.997	4.974 4.992 4.905	4.860 4.864 4.808	4.775 4.795 4.284
DEPTH TO INVERT	1.199	1.131 1.151	1.210 1.230	
INVERT LEVEL OF DRAIN	4.718	4.706 4.886	4.651 4.631	4.523 4.248
DESIGN SURFACE LEVEL	5.808	5.837	5.398	4.973
SETOUT COORDINATES	468527.10E 7174646.997N	468524.711E 7174649.550N	468527.118E 7174651.638N	468529.541E 7174653.364N
CHAINAGE	0.000	2.440 3.382	2.226 6.584	2.552 9.588 13.192

LINE 100

**APPROVED**

Name: Trudi Smith  
Date: 12:44 pm, 21/10/2024

Last Modified: Jul 30, 2024 - 1:42PM

2	100% Design Issue	19.07.2024
1	85% Design Review	07.06.2024
Revisions/Descriptions		Date
Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title		

Associated Job Nos	Survey Data
Auxiliary Drg Nos	Horiz. Datum: GDA2020 Horiz. Grid: MGA 56 Height Datum: AHD Survey Books: 200418 001 200418

Dimensions shown in metres except where shown otherwise

228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677
Through Chainage from				

DMTR EVENT 22A DRAINAGE LONGITUDINAL SECTIONS			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024

Job No. 2835872  
Contract No. CN-21784  
Drawing No. 953847 2  
Series Number DD-LS-01 of 01

LANDSCAPE LEGEND – SOFTWARES

**M1** **MIX TYPE 1 (M1) – REVEGETATION PLANTING – SHRUBS (CONTAINERISED)**

- AMELIORATE SUBSOIL – INCORPORATE AMELIORANT/S AT RATES AS PER THE CONTRACTOR’S SOIL MANAGEMENT PLAN
- ROUGHENING – 50mm DEEP (MINIMUM)
- CULTIVATION – 150mm DEEP (MINIMUM)
- TOPSOIL – 300mm AMELIORATED TOPSOIL (MINIMUM)
- MULCH – MULCH AS SPECIFIED
- FERTILISER – INCORPORATE FERTILISER AT RATES AS PER THE CONTRACTOR’S SOIL MANAGEMENT PLAN – CONSTRUCTION
- PLANTING – REFER TO PLANTING SCHEDULES FOR SPECIES AND DENSITIES
- DETAIL – REFER DTMR STANDARD DETAIL 1 & 2 ON DRAWING SD1653 (DATE 7/17, REV E)

**M2** **MIX TYPE 2 (M2) – REVEGETATION PLANTING – GROUNDCOVERS (CONTAINERISED)**

- AMELIORATE SUBSOIL – INCORPORATE AMELIORANT/S AT RATES AS PER THE CONTRACTOR’S SOIL MANAGEMENT PLAN
- ROUGHENING – 50mm DEEP (MINIMUM)
- CULTIVATION – 150mm DEEP (MINIMUM)
- TOPSOIL – 300mm AMELIORATED TOPSOIL (MINIMUM)
- MULCH – MULCH AS SPECIFIED
- FERTILISER – INCORPORATE FERTILISER AT RATES AS PER THE CONTRACTOR’S SOIL MANAGEMENT PLAN – CONSTRUCTION
- PLANTING – REFER TO PLANTING SCHEDULES FOR SPECIES AND DENSITIES
- DETAIL – REFER DTMR STANDARD DETAIL 1 & 2 ON DRAWING SD1653 (DATE 7/17, REV E)

**T1** **TURF (T1) – GREEN COUCH (CYNODON DACTYLON)**

- AMELIORATE SUBSOIL – INCORPORATE AMELIORANT/S AT RATES AS PER THE CONTRACTOR’S SOIL MANAGEMENT PLAN
- CULTIVATION – 150mm DEEP (MINIMUM)
- TOPSOIL – AMELIORATED TOPSOIL AS SPECIFIED
- FERTILISER – INCORPORATE FERTILISER AT RATES AS PER THE CONTRACTOR’S SOIL MANAGEMENT PLAN (CONSTRUCTION)
- TYPE – GREEN COUCH (CYNODON DACTYLON)
- DETAIL – REFER DTMR STANDARD DETAIL 1 & 2 ON DRAWING SD1650 (DATE 7/17, REV A)

**TE** **TIMBER EDGE (TE)**

- DETAIL – REFER DTMR STANDARD DETAIL 1603 (DATE 7/21, REV C)

**PROPOSED TREE (45L)**

- DETAIL – REFER PLANT SCHEDULES AND DTMR STANDARD DETAILS DETAIL 1 & 2 ON DRAWING SD1645 (DATE 7/21, REV C)

SURVEY AND GENERAL ARRANGEMENT LEGEND

- CONCRETE BATTER PROTECTION
- ROCK SCOUR PROTECTION
- PROPERTY BOUNDARY
- FENCE
- CONTROL LINE AND CHAINAGES
- TOP OF BATTER
- EXISTING ELECTRICITY O/H
- EXISTING GAS U/G
- EXISTING TELECOMMS U/G
- EXISTING WATER MAIN
- EXISTING SEWER RISING MAIN
- EXISTING STORMWATER
- EXISTING FEATURES
- EXISTING BATTER
- EXISTING KERB
- EXISTING SIGN – SINGLE
- EXISTING SIGN – DOUBLE
- EXISTING TREE
- EXISTING DRAINAGE FLOW PATH
- EXISTING FENCE
- EXISTING VEGETATION

Last Modified: 11 Jul 30, 2024 - 1:27PM

Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or - Full Name and Position Title	Date
2	100% Design Issue	19.07.2024
1	85% Design Review	28.06.2024

Associated Job Nos	Survey Data	Scales
	Horiz. Datum: GDA2020	NTS
	Auxiliary Drg Nos: Horiz. Grid: MGA 56	
	Height Datum: AHD	
	Survey Books: 200418 001, 200418	

228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE – GYMPIE ROAD CTL CHGE 2824 – 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677

DMTR EVENT 22A LANDSCAPE NOTES AND LEGEND SHEET 1 OF 2			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
CIVIL	MATT HAMILTON	16194	JULY 2024

**APPROVED**

Name: Trudi Smith  
Date: 12:44 pm, 21/10/2024

Job No.	2835872
Contract No.	CN-21784
Drawing No.	953848 2
Series Number	LR-NL-01 of 02







**LANDSCAPE SETBACK AND CLEARANCES**

NOTE: Refer to drawings 81404-81406 for Landscape setback and clearances schedule.

**CLARIFICATION OF TERMS**

- SETBACK:** Is measured from the outer edge of a design component, road element, object or carriageway line to the centre of the vegetation's (shrub or groundcover) trunk.
- CLEARANCE:** Is measured from the outer edge of a design component, road element, object or carriageway line to perimeter of the vegetation's (shrub or groundcover) mature canopy
- NON-FRANGIBLE VEGETATION:** Plants with stems larger than 100mm when measured from 300mm above the finished ground level. Shrubs species exceeding 3.5m in mature height and trees are considered non-frangible.
- FRANGIBLE VEGETATION:** Plants with stems or trunks equal to or less than 100mm when measured from 300mm above the finished ground level. Groundcovers and shrubs are all generally frangible except for large shrub species exceeding 3.5m in mature height. Trees are not considered frangible.
- GENERALLY:**
  - Planting is only to occur where a min. width of 3.0m is available. Where 3.0m is not achievable the area shall be concrete capped/paved.
  - Areas without road barriers: Frangible setback 1m from road pavement
- CLEAR ZONE:**
  - The Clear Zone line (extent) is shown as the interface between frangible and non-frangible revegetation barrier system occurs.

**DTMR STANDARD DRAWING REFERENCE**

Unless otherwise specifically approved by DTMR, all landscape works shall conform to MRTS16 (Date 7/17) and DTMR technical standards.

- SD1033\_KERB AND CHANNEL - PROFILES (Date 7/20, Rev L)
- SD1602\_CHAINWIRE FENCES AND GATES (Date 6/02, Rev B)
- SD1643\_VEGETATION GROUND WORKS: Planting container stock kerbed medians and separators (Date 7/17, Rev E)
- SD1644\_VEGETATION GROUND WORKS: Hardstand abutments to turf and planting beds (Date 7/17, Rev E)
- SD1650\_VEGETATION WORKS: Turfing (Date 7/17, Rev A)
- SD1653\_VEGETATION WORKS: Planting container stock <25L container (Date 7/17, Rev E)
- SD1654\_VEGETATION WORKS: Planting container stock >25L container (Date 7/17, Rev E)

**SETBACKS FROM SERVICES & UTILITIES**

For all vegetation and clearance requirements for Public Utility Plant (PUPs), services, street lighting, surveillance and drainage items, refer to the Vegetation Setback and Clearances Schedule (Refer Drgs 81013-81015). To be read in conjunction with Ergon's Plant Smart guidelines <https://www.ergon.com.au/network/safety/home-safety/trees-and-powerlines/plant-smart>

Note: The Contractor is to verify location of all above and below ground services prior to planting. refer applicable PUP, ITS and Lighting and Electrical drawing packages for locations.

**SIGNS GENERAL**

VEGETATION SETBACKS AND CLEARANCES:

Approach and departure road

- Signage mounted in accordance with the MUTCD.
- Vegetation within sight lines to have maximum mature height of 500mm below bottom edge of sign. Vegetation shall not impeded sight from 100-150m from edge of sign.

Note: Setbacks and clearances to its signage is to be set-out on site by Contractor in accordance with DMRTS requirements and approved by Administrator (size of poles, cabinets and signage may vary).

**VEGETATION PROTECTION NOTES**

- Clearing area shown on plans indicative only. All existing vegetation works which is to be retained is to be confirmed onsite with the Administrator. The Contractor is to minimise area of clearing and all clearing areas to be reinstated. All vegetation outside of the clearing and grubbing area is to be retained and protected in accordance with AS4970-2009.
- All existing trees and landscape works to be retained are to be protected from impact during construction activities in accordance with AS4970-2009 Protection of Trees on Development Sites.
- Existing vegetation that falls within sightlines, will be assessed on site and maintained as required.
- Any tree protection fencing to be installed is to be installed as per AS4970-2009.
- All works to be undertaken adjacent to existing vegetation is to be carried out in accordance with AS4970-2009 requirements. All excavation works within the TPZ (tree protection zones) are to be done by approved hand or vacuum methods. No stockpiling or storage of materials (including equipment) is allowed in TPZ.
- Weed management is to be in accordance with MRTS16 (Date 7/17) & MRTS04 General Earthworks (Date 3/20)
- Extent of clearing for site access and construction activities to be confirmed by Landscape Superintendent in relation to existing vegetation and habitat footprints being retained and protected. Works beyond the landscape treatments shown on plans to be confirmed and mitigated where possible.

**LANDSCAPE EROSION CONTROL MEASURES**

- Biodegradable organic matting is to be used on the batters of the disturbed waterways (where required).
- For all organic matting, including fixing and ground preparation (depth of soil, mulch, and planting), refer to DTMR standard drawing 1647 (Date 7/17, Rev E) and to follow the applicable manufacturer's specifications.
- For all landscape earthworks, stabilisation and surface preparation guidance, refer to MRTS16 (Date 7/17).
- All other erosion and sediment control measures to be in accordance with Construction Erosion and Sediment Control Plan (ESCP).

**LANDSCAPE SOIL NOTES**

- The Contractor is to prepare a Soil Management Plan (Construction) for DTMR approval prior to clearing and grubbing operations as per MRTS16 (Date 7/17) Clause 5.2.2.
- All subgrades to receive landscape treatments must be tested along with all topsoils used in the finished works in accordance with MRTS16 (Date 7/17) and ameliorated as determined in the Soil Management Plan by Contractor.
- All planting treatment types will utilise site won or imported mulch. Revegetation zones will utilise site won mulch in accordance with MRTS16 (Date 7/17). To be determined on site.
- In situ testing of the stripped topsoil is to be undertaken to verify the amelioration requirements in accordance with the proposed landscape design (in accordance with the requirements of Form C & D of MRTS16 (Date 7/17)). Further testing on the embankment material and stripped topsoil is to confirm/verify these properties, to ensure establishment and maintenance of the landscaping design is achievable and sustainable past the maintenance period.

**LANDSCAPE NOTES**

- All plans and details are to be read in conjunction with the legend, schedules and notes provided within the landscape package.
- All plans and details are to be read in conjunction with relevant engineering and environmental design documentation packages.
- Landscape works to be undertaken in accordance with Department of Transport and Main Roads Specification MRTS16 Landscape and Revegetation Works, associated Annexures and standard drawings (landscape and revegetation).
- All existing and retained elements are shown indicatively only. The location of these elements are based on survey information supplied by the Client, all works are to be setout and confirmed onsite prior to construction works.
- All underground services are to be confirmed by the contractor to ensure infrastructure is not damaged or interrupted by works. The Contractor is to liaise with service providers to gain all approvals/permits.
- Potential services conflicts, protection and/or relocation with initial works shall be determined prior to construction using current "dial before you dig" information, pot-holing and consultation with relevant services authorities.


- Do not scale directly from drawings. all other disciplinary elements are shown indicatively. Refer to the relevant package for the information
- The Contractor shall be responsible for the engagement of a registered surveyor for the setout of all project work.
- Clearing and grubbing shall be in accordance with MRTS04 General Earthworks (Date 3/20), MRTS16 Landscape and Revegetation Works (Date 7/17), MRTS51 Environmental Management (Date 11/19) and MRTS52 Erosion and Sediment Control (Date 7/18). Any additional conflicts shall be identified and resolved onsite with the Administrator.
- The works shall be constructed in accordance with the Contractor's approved work method where required.
- The Contractor shall remove all weeds during the establishment and maintenance periods in accordance with the Contractor's weed management plan and MRTS16 (Date 7/17) requirements.
- The Contractor shall provide and install temporary fencing to adequately define and secure the landscape works where required.
- Treatments are to remain within the road reserve and not extend into private property.
- Areas left blank (white space) are to be retained as existing and are generally characterised by low value grass cover within the corridor. Areas disturbed by the construction works shown to the extent of works shall be re-instated and receive a suitable landscape treatment determined by the Administrator, generally to match the treatment closest to the affected area.

**REFERENCE SPECIFICATIONS**

- For Landscape and Revegetation, refer to Annexure MRTS16.1 Landscape and Revegetation Works (Date 7/17)
- For Anti-graffiti coatings to structures, refer to Annexure MRTS83.1 Anti-Graffiti Protection (Date 11/19)
- For painting treatments to structures, refer to Annexure MRTS88.1 Protective Coating for New Work (Date 7/17)
- For General Earthworks, refer to Annexure MRTS04 - General Earthworks (Date 3/20)
- For Environmental Management, refer to Annexure MRST51 Environmental Management (Date 11/19)
- For Erosion and Sediment Control, refer to Annexure MRTS52 Erosion and Sediment Control (Date 7/18)

Last Modified: 1 Jul 30, 2024 - 1:53PM

		Associated Job Nos	Survey Data		Scales	228 FRASER COAST REGIONAL COUNCIL					DMTR EVENT 22A					
			Horiz. Datum	GDA2020		163 LAMINGTON BRIDGE - GYMPIE ROAD					LANDSCAPE NOTES AND LEGEND					
		Auxiliary Drg Nos	Horiz. Grid	MGA 56	NTS	CTL CHGE 2824 - 2905					SHEET 2 OF 2					
2		100% Design issue	Height Datum	AHD		Reference Points					ENGINEERING CERTIFICATION (RPEQ)					
1		85% Design Review	Survey Books	200418 001 200418	Dimensions shown in millimeters except where shown otherwise	Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP	ENG. AREA	SIGNATORY FULL NAME	No.	DATE	Contract No.	CN-21784
		Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title	Date		PSM 44312	0.07	0.08	0.18	PSM 15677	CIVIL	MATT HAMILTON	16194	JULY 2024	Drawing No.	953849 2
						Through Chainage from									Series Number	LR-NL-02 of 02





Road Landscape Manual (extract)  
Appendix 4 – Vegetation Setbacks and Clearances

**MINIMUM VEGETATION SETBACK AND CLEARANCES SCHEDULE**

Setbacks and clearances relate to horizontal distances only. Where related to vertical distances, these are noted otherwise.

Parameter	Description: Non-frangible verse frangible vegetation	Setback	Clearances	Value	Rationale
Roadside areas without barriers	All non-frangible vegetation; measured from carriageway edge line to clear zone	✓		As per RPDM	RPDM (in conjunction with Austroads) is a higher order document.
Roadside areas with barriers	Non-frangible vegetation; Concrete barriers	✓		1.5m	Provides maintenance free treatment to rear of barrier.
	Frangible vegetation; Concrete barriers	✓		0.5m or ½ Dia*	
	Non-frangible vegetation; Wire rope barriers	✓		2.0m	Allows for deflection/movement of the barrier when impacted.
	Frangible vegetation; Wire rope barriers	✓		0.5m or ½ Dia*	
	Non-frangible vegetation; W-beam & TRS Beam barriers (also includes a 'hazard free zone', which typically extends 6m behind the back of the guardrail and for 22.5m from each end)	✓		1.0m	
	Frangible vegetation; Steel barriers (also includes a 'hazard free zone', which typically extends 6m behind the back of the guardrail and for 22.5m from each end)	✓		1.0m	
Roadside general	Non-frangible vegetation (general); from road pavement edge	✓		2.5m **A	Setback required mitigating potential tree root damage and resulting reduction of life to road pavement. Greater offsets are required for species with known invasive root systems (eg., Ficus and Melaleuca species).
	Non-frangible vegetation (general); from road pavement edge		✓	7.0m	The projected/anticipated canopy line of trees should not encroach beyond the outer carriageway line or be capable of providing a canopy within the minimum 7m clearance adjacent to trafficked lanes in the future.
	Non-frangible vegetation (>15m in mature height known to have a reputation of limb drop and/or large seed drop during high wind/storm events); from road pavement edge	✓		10.0m	To mitigate the risk of trees, limbs, branches and large seeds falling and impacting the roadway (eg. Eucalyptus species).
	Frangible vegetation		✓	0.5m or ½ Dia*	To prevent planting overhanging roadway; reducing potential for safety obstructions and increased maintenance requirements.
Roadside structures and furniture	Non-frangible vegetation; tree canopy from fauna fence (relative to rear/ fauna side of fence)		✓	3.0m **B	Eliminates the risk of fauna (koalas in particular) dropping into the fenced road corridor which may be difficult/ impossible for the fauna to escape
	Non-frangible vegetation; from outer parapet/ rails and piers of bridges	✓		5.0m	Minimises the likelihood of the bridge being impacted by trees; both structurally and from a maintenance perspective (protects from strike). Also reduces likelihood of vegetation encroaching sightlines. NOTE – greater setbacks may be required in those parts of Queensland where intense storms/ cyclones are a regular occurrence.
	Non-frangible vegetation; either side of retaining structures as per RPEQ's determination		✓	As per RPEQ	Requirements of walls vary depending on type and site conditions. RPEQ to ensure trees do not compromise walls integrity, over its required design life.
	Frangible vegetation (general); includes but not limited to fencing, retaining walls, kerbs, garden edging, drainage channels**C		✓	0.5m or ½ Dia*	Maintenance minimisation; retains structure/ furniture function and reduces the likelihood of conflict between the vegetation and adjoining structure or edge.
	Frangible vegetation; from fauna fence (relative to rear/ fauna side of fence)	✓		1.0m (ground covers) and 1.5m shrubs	Applies to wide corridors only; that is, where space permits for maintenance access. Narrow corridors which lack of space behind fauna fence do not apply as an additional setback will further reduce vegetation coverage, compromising corridor effectiveness and habitat connectivity. Similarly, corridors where there is a guard rail absent do not apply as have sufficient space available to front/ road side of fence for maintenance access through clear zone and setback requirements and results in no further need for maintenance access on other rear/ fauna side of fence.
Maintenance access paths/ tracks	Non-frangible vegetation	✓		1.0m	Allows for maintenance track to remain operational. NOTE – crown lifting may be required to facilitate.
	Frangible vegetation		✓	0.5m or ½ Dia*	Maintenance minimisation and reduces conflicts with safety hazards for operational staff
Noise barriers (where maintenance access is required)	Non-frangible vegetation		✓	1.5m	Also allows for maintenance access. Clearance eliminates conflict between tree and wall and beyond.
	Frangible vegetation		✓	1.0m	Allows for maintenance access
Road Signage	Approach side 1. Vegetation within sightline triangle – clearance as indicated 2. Vegetation within sightline triangle having maximum mature height of 500mm below bottom edge of sign – No requirements necessary. 3. In addition to notes 1 & 2 all vegetation to comply with RP & D manual and/or clear zone and sight visibility requirements where present..	✓			•Ensure sight distance triangles across road landscapes (with horizontal curvature) are achieved so that the driver has time to recognise and react to the sign. •Vegetation that will block sightline, longitudinal sight distance triangle start point to be minimum of 1.4V m in advance of the sign (where V is the 85th percentile speed) and sighted to far outside edge of sign. Eye measurement to be taken to centre of traffic lane. •For sight-distance calculations refer to RP & D manual •For sign location/ placement refer to MUTCD

**APPROVED**

Name: Trudi Smith  
Date: 12:45 pm, 21/10/2024

Last Modified: 11 Jul 30, 2024 - 1:58PM

Associated Job Nos		Survey Data		Scales	228 FRASER COAST REGIONAL COUNCIL					DMTR EVENT 22A						
		Horiz. Datum: GDA2020			NTS	163 LAMINGTON BRIDGE – GYMPIE ROAD					SETBACK AND CLEARANCES SCHEDULE					
Auxiliary Drg Nos		Horiz. Grid: MGA 56				CTL CHGE 2824 – 2905					SHEET 1 OF 3					
		Height Datum: AHD			Reference Points					ENGINEERING CERTIFICATION (RPEQ)						
2 100% Design issue		19.07.2024			Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP	ENG. AREA	SIGNATORY FULL NAME		No.	DATE	Job No.	2835872
1 85% Design Review		28.06.2024			PSM 44312	0.07	0.08	0.18	PSM 15677	CIVIL	MATT HAMILTON		16194	JULY 2024	Contract No.	CN-21784
Revisions/Descriptions		Signatory: – RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title			Dimensions shown in millimeters except where shown otherwise										Drawing No.	953850   2
		Date			Through Chainage from										Series Number	LR-NL-03 of 03





Road Landscape Manual (extract)  
Appendix 4 – Vegetation Setbacks and Clearances

### MINIMUM VEGETATION SETBACK AND CLEARANCES SCHEDULE

Setbacks and clearances relate to horizontal distances only. Where related to vertical distances, these are noted otherwise.

Parameter	Description: Non-frangible verse frangible vegetation	Setback	Clearances	Value	Rationale
	Departure side 1. Single-sided signs with frangible vegetation – maintenance area requirements apply as indicated. 2. Double-sided signs need to comply with notes 1 & 2 for approach situations. 3. In addition to notes 1 & 2 all vegetation to comply with RP & D manual and/or clear zone and sight visibility requirements where present.	✓ ✓ ✓		Single-sided signs:– 10.0m (Min) • Double-sided signs • As per approach side above	Ensures sign is not obstructed by any vegetation and assists with maintenance operations. Sightlines are retained **D
Sight Distance	Vegetation sight distance triangle; Plantings in these zones should provide a clear visibility both horizontally and vertically when the eye height and the target height are considered.		✓	• Sight distance as per RPDM • Proposed mature plantings and landform combination heights should be at least 100mm outside the vertical limits of the sight triangle	RPDM (in conjunction with Austroads) is a higher order document. Ensures sight distance is not obstructed by vegetation enabling drivers to have sufficient time to observe and react accordingly, also minimising maintenance and ensuring sightlines are retained
Pedestrian and Cyclist Environments	Non-frangible vegetation (general); from pavement edge – pathway, cycleway or other	✓		1.0m	Setback ensures trees will provide shade to pedestrian/ cyclist areas and nodes**E
	Non-frangible vegetation (>15m in mature height known to fall or have a reputation of limb drop and/or large seed drop during high wind/storm events; or plants with aggressive/ spreading root system); from pavement edge – pathway, cycleway or other	✓		10.0m	To mitigate the risk of trees, limbs, branches and large seeds falling and impacting on pedestrian/ cyclist areas and nodes (eg. Eucalyptus species). To mitigate potential tree root damage and resulting reduction of life to pavement surface, for species with known invasive root systems (eg., Ficus and Melaleuca species).
	Frangible vegetation		✓	0.5m or ½ Dia*	To prevent planting overhanging pathways, cycleways or other; reducing potential for safety obstructions and increased maintenance requirements
Lighting (Roadway 3 10.0m Indicative only**F Lighting only) – For Street Lighting/ Public Lighting; refer directly to Local Authority requirements	Non-frangible vegetation and Frangible vegetation (greater than 4m in height)	✓		10.0m	Indicative Only **F
	Frangible vegetation (all other)	✓		1.0m	To retain a clear surround for maintenance access.
CCTV view–shed	Vegetation below view–shed		✓	Maximum mature height of 1.0m below bottom edge of view–shed	To prevent planting encroaching view–shed; reducing potential for obstructions and maintenance requirements
	Vegetation beside view–shed	✓		½ mature diameter	
Above ground Electrical Services (relative to Energex, Ergon Energy and Energy Australia requirements ONLY) – For Powerlink (High Voltage Transmission Lines) setbacks and clearances; refer directly to Powerlink requirements	≤33kV (low voltage line) –Below powerlines: Frangible vegetation or 'Energex's Safe Tree plants' (3.5m maximum mature height for min. 7.0m either side of alignment –Refer further to below requirement)			n/a – mature height will be below actual line	To ensure conflict does not occur between vegetation and power infrastructure (lines, conductors, poles and so on) and minimise potential ongoing maintenance required to retain clearances as per PUP owners' requirements.
	≤ 33kV (low voltage line) –Near powerlines, including poles: Non-frangible vegetation (45° rule; as per 'Energex's Safe Tree Program').		✓	To equal at least mature height or min 7.0m (that which is greater)	
	> 33kV (high voltage line) –Below powerlines: Frangible vegetation or 'Energex's Safe Tree plants' (3.5m maximum mature height for min. 10.0m either side of alignment –Refer further to below requirement)		✓	4.0m	
	>33kV (high voltage line) –Near powerlines, including poles: Non-frangible vegetation (45° rule; as per 'Energex's Vegetation management Standard').			n/a mature height will be below actual line	
	> 33kV (high voltage line) –Around poles: Frangible vegetation		✓	To equal at least mature height, or min 10.0m (that which is greater)	
	Substations, tower structures and any other facilities (generally 2.0m standard however often by negotiation with owner): Frangible		✓	6.0m	
Underground water (including drainage and sewerage), electrical or any other underground services; telecommunications and fibre optics**G	All vegetation with mature height ≤3.5m	✓		2.0m	To allow future access and minimise impacts to underground services from root systems
	All vegetation with a mature height >2.5m (general underground services and piping)	✓		As per arborist advice or min 4.0m (that which is greater)	To ensure tree roots do not impact on underground infrastructure –setback will vary with species characteristics; that is, greater setbacks required for species with vigorous or known to be invasive root systems.
	All vegetation with a mature height >3.5m (drainage sump)	✓		As per arborist advice or min. 6.0m (that which is greater)	



Last Modified: 1 Jul 30, 2024 - 1:53PM

Associated Job Nos		Survey Data		Scales	<b>228 FRASER COAST REGIONAL COUNCIL</b>					<b>DMTR EVENT 22A</b>					
		Horiz. Datum: GDA2020			<b>163 LAMINGTON BRIDGE – GYMPIE ROAD</b>					<b>SETBACK AND CLEARANCES SCHEDULE</b>					
Auxiliary Drg Nos		Horiz. Grid: MGA 56		NTS	<b>CTL CHGE 2824 – 2905</b>					<b>SHEET 2 OF 3</b>					
		Height Datum: AHD			Reference Points					ENGINEERING CERTIFICATION (RPEQ)					
2 100% Design issue		19.07.2024		Dimensions shown in millimeters except where shown otherwise	Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP	ENG. AREA	SIGNATORY FULL NAME	No.	DATE	Job No.	2835872
1 85% Design Review		28.06.2024			PSM 44312	0.07	0.08	0.18	PSM 15677	CIVIL	MATT HAMILTON	16194	JULY 2024	Contract No.	CN-21784
Revisions/Descriptions		Signatory: – RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title		Survey Books	200418 001 200418		Through Chainage from						Drawing No.	953851 2	
CAD FILES		AECOM_DS13_AU\Documents\60701625-TMR WBB REPA\900_CAD_GIS\910_CAD\20_Sheets\Civil\60701625-ACM-3001-910-300-DRG-81014-LR-NL												Series Number	LR-NL-04 of 03









PLANTING SCHEDULES:

<b>TURF TYPE 1 (T1) - GREEN COUCH (CYNODON DACTYLON)</b>		
AREA (m <sup>2</sup> )	=	1226

<b>MIX TYPE A TREES - SHADE TREES (CONTAINERISED PLANTING)</b>							
CODE	BOTANICAL NAME	COMMON NAME	CONTAINER SIZE	DENSITY	MATURE HEIGHT (m)	MATURE SPREAD (m)	QTY
EUC ter	<i>Eucalyptus tereticomis</i>	Queensland Blue Gum	45L	As Shown	30	12	5
<b>TOTAL</b>						=	<b>5</b>

<b>MIX TYPE 1 (M1) - REVEGETATION PLANTING - LARGE SHRUBS (CONTAINERISED)</b>							
					AREA (m <sup>2</sup> )	=	51
CODE	BOTANICAL NAME	COMMON NAME	CONTAINER SIZE	DENSITY (per m2)	MATURE HEIGHT (m)	MATURE SPREAD (m)	QTY
<b>TREE SPECIES</b>							
ACA dis	<i>Acacia disparima</i>	Hickory Wattle	140mm	3	5	4	26
ACA mai	<i>Acacia maidenii</i>	Maidens Wattle	140mm		10	5	26
BAN spi	<i>Banksia spinulosa</i>	Hairspin Banksia	140mm		3	2	26
ELO obo	<i>Elaeocarpus obovatus</i>	Blueberry Ash	140mm		8	4	26
MEL lin	<i>Melaleuca linariifolia</i>	Narrow Leaved Paperbark	140mm		7	3	26
MEL vim	<i>Melaleuca viminalis</i>	Weeping Bottlebrush	140mm		4	3	26
<b>TOTAL</b>						=	<b>153</b>


<b>MIX TYPE 2 (M2) - REVEGETATION PLANTING - GRASSES (CONTAINERISED)</b>							
					AREA (m <sup>2</sup> )	=	35
CODE	BOTANICAL NAME	COMMON NAME	CONTAINER SIZE	DENSITY (per m2)	MATURE HEIGHT (m)	MATURE SPREAD (m)	QTY
GAH asp	<i>Gahnia aspera</i>	Rough Saw-Sedge	140mm	4	1.5	1.5	35
LOM hys	<i>Lomandra hystrix</i>	Green Matrush	140mm		1	1	35
LOM lon	<i>Lomandra longifolia</i>	Long-Leaf Matrush	140mm		1.2	1.2	35
THE tri	<i>Themeda triandra</i>	Kangaroo Grass	140mm		1.5	0.3	35
<b>TOTAL</b>						=	<b>140</b>



Last Modified: 11 Jul 30, 2024 - 1:15:41PM

		Associated Job Nos	Survey Data		Scales  NTS	<b>228 FRASER COAST REGIONAL COUNCIL</b>				<b>DMTR EVENT 22A</b>					
			Horiz. Datum	GDA2020		<b>163 LAMINGTON BRIDGE - GYMPIE ROAD</b>				<b>LANDSCAPE SCHEDULE</b>					
		Auxiliary Drg Nos	Horiz. Grid	MGA 56		<b>CTL CHGE 2824 - 2905</b>				<b>SHEET 1 OF 1</b>					
			Height Datum	AHD	Reference Points				ENGINEERING CERTIFICATION (RPEQ)						
2	100% Design issue				Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP	ENG. AREA	SIGNATORY FULL NAME	No.	DATE	Job No.	2835872
1	85% Design Review				PSM 44312	0.07	0.08	0.18	PSM 15677	CIVIL	MATT HAMILTON	16194	JULY 2024	Contract No.	CN-21784
Revisions/Descriptions		Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or - Full Name and Position Title	Date	Survey Books	Dimensions shown in millimeters except where shown otherwise								Drawing No.	953853 2	
CAD FILES   AECOM_DS13_AU\Documents\60701625-TMR WBB REPA\900_CAD_GIS\910_CAD\20_Sheets\Civil\60701625-ACM-3001-910-300-DRG-81016-LR-NL														Series Number	LR-NL-06 of 01

Contractor to consult with arborist and adjust earthworks extents surrounding the existing trees identified as being retained. Works surrounding existing trees Tree Protection Zones to be in accordance with AS4970-2009 and project arborist recommendations



Last Modified: 1:14:52PM Jul 30, 2024

2	100% Design issue	19.07.2024
1	85% Design Review	28.06.2024
Revisions/Descriptions		Date
Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title		

Associated Job Nos	Survey Data
Auxiliary Drg Nos	Horiz. Datum: GDA2020
	Horiz. Grid: MGA 56
	Height Datum: AHD
Survey Books	200418 001 200418


Dimensions shown in metres except where shown otherwise

228 FRASER COAST REGIONAL COUNCIL				
163 LAMINGTON BRIDGE - GYMPIE ROAD				
CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677
Through Chainage from				

DMTR EVENT 22A LANDSCAPE LAYOUT SHEET 1 OF 1			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
CIVIL	MATT HAMILTON	16194	JULY 2024

Job No.	2835872
Contract No.	CN-21784
Drawing No.	953854 2
Series Number	LR-LD-01 of 01

TURFED AREA      M2 - GRASSES      M1 - LARGE SHRUBS      M2 - GRASSES      RETAINING WALL - REFER CIVIL ENGINEERS DOCUMENTATION



01 LAMINGTON BRIDGE LANDSCAPE REHABILITATION SECTION  
1:25

**APPROVED**

Name: Trudi Smith  
Date: 12:46 pm, 21/10/2024

Last Modified: 11 Jul 30, 2024 - 1:42PM

2	100% Design issue	19.07.2024
1	85% Design Review	28.06.2024
Revisions/Descriptions		Date
Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title		

Associated Job Nos	Survey Data
Auxiliary Drg Nos	Horiz. Datum: GDA2020
	Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418

Scales

Dimensions shown in millimeters except where shown otherwise


228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677
Through Chainage from				

DMTR EVENT 22A LANDSCAPE SECTION SHEET 1 OF 1			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
CIVIL	MATT HAMILTON	16194	JULY 2024


Job No. 2835872  
Contract No. CN-21784  
Drawing No. 953855 2  
Series Number LR-GD-01 of 01




LEGEND	
	Existing Surface
	Earthworks Cut
	Design
	Tide Levels




CHAINAGE 2.000



CHAINAGE 6.000



CHAINAGE 0.000



CHAINAGE 4.000

**APPROVED**

Name: Trudi Smith  
Date: 12:46 pm, 21/10/2024

Last Modified: 21 Jul 30, 2024 - 1:45PM

Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or - Full Name and Position Title	Date
4 100% Design Issue		19.07.2024
3 85% Design Review		07.06.2024
2 50% Design Review		17.05.2024
1 30% Design Review		04.03.2024

Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
	Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418

Dimensions shown in metres except where shown otherwise

228 FRASER COAST REGIONAL COUNCIL  
163 LAMINGTON BRIDGE - GYMPIE ROAD  
CTL CHGE 2824 - 2905

Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677

Through Chainage from


DMTR EVENT 22A  
ANNOTATED CROSS SECTIONS  
CONTROL LINE MW300101 - SHEET 1

ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024


Job No. 2835872  
Contract No. CN-21784  
Drawing No. 953856 4  
Series Number XS-01 of 11




LEGEND	
	Existing Surface
	Earthworks Cut
	Design
	Tide Levels




CHAINAGE 10.000



CHAINAGE 14.000



CHAINAGE 8.000




CHAINAGE 12.000

Last Modified: Jul 30, 2024 - 1:45PM

Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title	Date
4 100% Design Issue		19.07.2024
3 85% Design Review		07.06.2024
2 50% Design Review		17.05.2024
1 30% Design Review		04.03.2024

Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
	Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418



228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677
Through Chainage from				


DMTR EVENT 22A ANNOTATED CROSS SECTIONS CONTROL LINE MW300101 - SHEET 2			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024

**APPROVED**


Name: Trudi Smith  
Date: 12:46 pm, 21/10/2024

Queensland Government	
Job No.	2835872
Contract No.	CN-21784
Drawing No.	953857 4
Series Number	XS-02 of 11


LEGEND	
	Existing Surface
	Earthworks Cut
	Design
	Tide Levels




CHAINAGE 18.000



CHAINAGE 22.000



CHAINAGE 16.000



CHAINAGE 20.000

**APPROVED**

Name: Trudi Smith  
Date: 12:46 pm, 21/10/2024

Last Modified: 11 Jul 30, 2024 - 1:45PM

Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title	Date
4 100% Design Issue		19.07.2024
3 85% Design Review		07.06.2024
2 50% Design Review		17.05.2024
1 30% Design Review		04.03.2024

Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
	Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418

Dimensions shown in metres except where shown otherwise

228 FRASER COAST REGIONAL COUNCIL  
163 LAMINGTON BRIDGE - GYMPIE ROAD  
CTL CHGE 2824 - 2905

Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677

Through Chainage from


DMTR EVENT 22A  
ANNOTATED CROSS SECTIONS  
CONTROL LINE MW300101 - SHEET 3

ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024

Job No.	2835872
Contract No.	CN-21784
Drawing No.	953858 4
Series Number	XS-03 of 11



**GPC Gladstone Ports Corporation**  
**APPROVED**  
 Name: Trudi Smith  
 Date: 12:47 pm, 21/10/2024



**MODEL : CONTROL 3001 EWK - STRING : MK300190**

PT	CHAINAGE	EASTING	NORTHING	HEIGHT	BEARING	DEP.SEG
Start	35.000	468481.127	7174618.902	8.347	38°54'58.31"	LINE
	40.000	468484.268	7174622.792	8.111	38°54'58.31"	
	45.000	468487.409	7174626.683	7.875	38°54'58.31"	
	50.000	468490.550	7174630.573	7.639	38°54'58.31"	
	55.000	468493.691	7174634.463	7.403	38°54'58.31"	
	60.000	468496.832	7174638.354	7.167	38°54'58.31"	
	65.000	468499.973	7174642.244	6.931	38°54'58.31"	
	70.000	468503.113	7174646.134	6.695	38°54'58.31"	
	75.000	468506.254	7174650.025	6.459	38°54'58.31"	
End	77.500	468507.825	7174651.970	6.341	38°54'58.31"	

**MODEL : CONTROL 3001 EWK - STRING : MK300191**

PT	CHAINAGE	EASTING	NORTHING	HEIGHT	BEARING	DEP.SEG
Start	-3.216	468502.785	7174656.039	7.438	128°54'59.08"	LINE
	0.000	468505.287	7174654.019	6.439	128°54'59.08"	
	5.000	468509.177	7174650.878	6.302	128°54'59.08"	
	10.000	468513.068	7174647.737	6.189	128°54'59.08"	
	15.000	468516.958	7174644.596	6.076	128°54'59.08"	
	20.000	468520.848	7174641.455	5.967	128°54'59.08"	
End	20.532	468521.262	7174641.121	5.956	128°54'59.08"	

**MODEL : CONTROL 3001 EWK - STRING : MK300192**

PT	CHAINAGE	EASTING	NORTHING	HEIGHT	BEARING	DEP.SEG
Start	0.000	468476.846	7174622.358	10.181	128°54'58.05"	LINE
	5.000	468480.737	7174619.217	8.352	128°54'58.05"	
	10.000	468484.627	7174616.076	8.304	128°54'58.05"	
	15.000	468488.517	7174612.935	8.258	128°54'58.05"	
	20.000	468492.408	7174609.795	8.211	128°54'58.05"	
End	22.039	468493.994	7174608.514	8.192	128°54'58.05"	

**LEGEND**

	Property Boundary		Existing Features
	Control Line and Chainages		Batter
	Top of Batter		Existing Kerb
	Existing Electricity O/H (Survey)		Existing Guardrail
	Existing Gas U/G (Survey)		Sign - Single
	Existing Telecomms U/G (Survey)		Sign - Double
	Existing Water Main (Survey)		Tree
	Existing Sewer Main (Survey)		Drainage Flow Path
	Existing Stormwater		Fence

Last Modified: 1: Jul 30, 2024 - 1:42PM

Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or - Full Name and Position Title	Date
3 100% Design Issue		19.07.2024
2 85% Design Review		07.06.2024
1 50% Design Review		17.05.2024

Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
	Auxiliary Drg Nos: Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418

**228 FRASER COAST REGIONAL COUNCIL**  
**163 LAMINGTON BRIDGE - GYMPIE ROAD**  
**CTL CHGE 2824 - 2905**

Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677


Through Chainage from

**DMTR EVENT 22A EARTHWORKS LAYOUT**

ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024


**Queensland Government**

Job No. 2835872  
 Contract No. CN-21784  
 Drawing No. 953859 3  
 Series Number EW-LD-01 of 01




CONTROL LINE MK300190

HORIZONTAL - 1:200  
VERTICAL - 1:200



CONTROL LINE MK300191

HORIZONTAL - 1:200  
VERTICAL - 1:200



CONTROL LINE MK300192


HORIZONTAL - 1:200  
VERTICAL - 1:200



Last Modified: Jul 30, 2024 - 1:45PM

3	100% Design Issue	19.07.2024
2	85% Design Review	07.06.2024
1	50% Design Review	17.05.2024
Revisions/Descriptions		Date
Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title		Date

Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
Auxiliary Drg Nos	Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418




228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677
Through Chainage from				

DMTR EVENT 22A LONGITUDINAL SECTIONS CONTROL LINE MK300190, 191 & 192			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024


Queensland Government	
Job No.	2835872
Contract No.	CN-21784
Drawing No.	953860 3
Series Number	LS-03 of 04




LEGEND	
	Existing Surface
	Design
	Temporary Access Track




CHAINAGE 40.000



CHAINAGE 35.000



CHAINAGE 50.000



CHAINAGE 45.000

**APPROVED**

Name: Trudi Smith  
 Date: 12:47 pm, 21/10/2024

Last Modified: 1 Jul 30, 2024 - 1:42PM

Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title	Date
3 100% Design Issue		19.07.2024
2 85% Design Review		07.06.2024
1 50% Design Review		17.05.2024

Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
Auxiliary Drg Nos	Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418

Dimensions shown in metres except where shown otherwise

**228 FRASER COAST REGIONAL COUNCIL**  
**163 LAMINGTON BRIDGE - GYMPIE ROAD**  
**CTL CHGE 2824 - 2905**

Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677


Through Chainage from

**DMTR EVENT 22A**  
**ANNOTATED CROSS SECTIONS**  
**CONTROL LINE MK300190 - SHEET 1**


ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024

Job No. 2835872  
 Contract No. CN-21784  
 Drawing No. 953861 3  
 Series Number XS-04 of 11


LEGEND	
	Existing Surface
	Design
	Temporary Access Track




CHAINAGE 60.000



CHAINAGE 70.000



CHAINAGE 55.000



CHAINAGE 65.000

**APPROVED**

Name: Trudi Smith  
 Date: 12:47 pm, 21/10/2024

Last Modified: 11 Jul 30, 2024 - 1:42PM

Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title	Date
3 100% Design Issue		19.07.2024
2 85% Design Review		07.06.2024
1 50% Design Review		17.05.2024

Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
	Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418

Dimensions shown in metres except where shown otherwise

228 FRASER COAST REGIONAL COUNCIL  
 163 LAMINGTON BRIDGE - GYMPIE ROAD  
 CTL CHGE 2824 - 2905

Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677

Through Chainage from

DMTR EVENT 22A  
 ANNOTATED CROSS SECTIONS  
 CONTROL LINE MK300190 - SHEET 2

ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024

Job No. 2835872  
 Contract No. CN-21784  
 Drawing No. 953862 3  
 Series Number XS-05 of 11

LEGEND	
	Existing Surface
	Design
	Temporary Access Track

CENTRELINE DATA  
 E = 468507.825  
 N = 7174651.970  
 Z = 6.362

DATUM 1.00

DESIGN LEVELS	7.438	6.446				
EXISTING LIDAR	7.438	7.428				
EXISTING SURFACE	7.438	7.428				
OFFSETS	-6.477	-3.500		15.270	17.269	



CHAINAGE 77.500

CENTRELINE DATA  
 E = 468506.254  
 N = 7174650.025  
 Z = 6.459

DATUM 2.00

DESIGN LEVELS	7.730	6.564	6.459	6.230	6.043	6.003
EXISTING LIDAR	7.730	7.778	7.802	7.577	6.690	6.003
EXISTING SURFACE	7.730	7.778	7.802	7.577	6.690	6.003
OFFSETS	-6.562	-3.500	0.000	7.493	15.096	17.096

CHAINAGE 75.000



Last Modified: 11 Jul 30, 2024 - 1:42PM


Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title	Date
3 100% Design Issue		19.07.2024
2 85% Design Review		07.06.2024
1 50% Design Review		17.05.2024

Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
	Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418


228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677

DMTR EVENT 22A ANNOTATED CROSS SECTIONS CONTROL LINE MK300190 - SHEET 3			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024


Queensland Government	
Job No.	2835872
Contract No.	CN-21784
Drawing No.	953863 3
Series Number	XS-06 of 11




CHAINAGE 0.000




CHAINAGE 10.000



CHAINAGE -3.216



CHAINAGE 5.000




CHAINAGE 15.000



Last Modified: 1: Jul 30, 2024 - 1:45PM

3	100% Design Issue	19.07.2024
2	85% Design Review	07.06.2024
1	50% Design Review	17.05.2024
Revisions/Descriptions		Date
Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title		Date

Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
Auxiliary Drg Nos	Horiz. Grid: MGA 56
	Height Datum: AHD
Survey Books	200418 001 200418



228 FRASER COAST REGIONAL COUNCIL				
163 LAMINGTON BRIDGE - GYMPIE ROAD				
CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677
Through Chainage from				

DMTR EVENT 22A ANNOTATED CROSS SECTIONS CONTROL LINE MK300191			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024

Job No.	2835872
Contract No.	CN-21784
Drawing No.	953864 3
Series Number	XS-07 of 11







CENTRELINE DATA  
 E = 468484.627  
 N = 7174616.076  
 Z = 8.312

DATUM 6.00

DESIGN LEVELS		10.110	8.312
EXISTING SURFACE		0.000	
OFFSETS			

CHAINAGE 10.000

CENTRELINE DATA  
 E = 468480.737  
 N = 7174619.217  
 Z = 8.352

DATUM 6.00

DESIGN LEVELS		10.096	8.352
EXISTING SURFACE		0.000	
OFFSETS			

CHAINAGE 5.000

CENTRELINE DATA  
 E = 468492.408  
 N = 7174609.795  
 Z = 8.232

DATUM 5.00

DESIGN LEVELS		8.232	8.766
EXISTING SURFACE		8.576	8.766
OFFSETS		0.000	3.201

CHAINAGE 20.000

CENTRELINE DATA  
 E = 468476.846  
 N = 7174622.358  
 Z = 10.181

DATUM 8.00

DESIGN LEVELS		10.180	10.181
EXISTING SURFACE		0.000	0.000
OFFSETS			

CHAINAGE 0.000

CENTRELINE DATA  
 E = 468488.517  
 N = 7174612.935  
 Z = 8.272

DATUM 6.00

DESIGN LEVELS		8.272	10.011
EXISTING SURFACE		9.546	10.011
OFFSETS		0.000	10.434

CHAINAGE 15.000



Last Modified: 11 Jul 30, 2024 - 1:42PM

3	100% Design Issue	19.07.2024
2	85% Design Review	07.06.2024
1	50% Design Review	17.05.2024
Revisions/Descriptions		Date
Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title		Date

Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
Auxiliary Drg Nos	Horiz. Grid: MGA 56
	Height Datum: AHD
Survey Books	200418 001 200418


Scales

Dimensions shown in metres except where shown otherwise

228 FRASER COAST REGIONAL COUNCIL				
163 LAMINGTON BRIDGE - GYMPIE ROAD				
CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677
Through Chainage from				

DMTR EVENT 22A ANNOTATED CROSS SECTIONS CONTROL LINE MK300192			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024

Job No.	2835872
Contract No.	CN-21784
Drawing No.	953865 3
Series Number	XS-08 of 11



**LEGEND**

	Property Boundary		Existing Features
	Control Line and Chainages		Batter
	Top of Batter		Existing Kerb
	Existing Electricity O/H (Survey)		Existing Guardrail
	Existing Gas U/G (Survey)		Sign - Single
	Existing Telecomms U/G (Survey)		Sign - Double
	Existing Water Main (Survey)		Tree
	Existing Sewer Main (Survey)		Drainage Flow Path
	Existing Stormwater		Fence

Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or - Full Name and Position Title	Date
3 100% Design Issue		19.07.2024
2 85% Design Review		07.06.2024
1 50% Design Review		17.05.2024


Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
	Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418

228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677

DMTR EVENT 22A TEMPORARY ACCESS TRACK LAYOUT			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024

	<b>Queensland Government</b>
Job No.	2835872
Contract No.	CN-21784
Drawing No.	953866 3
Series Number	CS-LD-01 of 01

Last Modified: 1:14:52 PM Jul 30, 2024



CONTROL LINE MC300110

**APPROVED**  
Name: Trudi Smith  
Date: 12:48 pm, 21/10/2024

Last Modified: 1 Jul 30, 2024 - 1:42PM





Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or - Full Name and Position Title	Date
3 100% Design Issue		19.07.2024
2 85% Design Review		07.06.2024
1 50% Design Review		17.05.2024

Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
	Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418

228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677

DMTR EVENT 22A LONGITUDINAL SECTIONS CONTROL LINE MC300110			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024

Queensland Government	
Job No.	2835872
Contract No.	CN-21784
Drawing No.	953867 3
Series Number	LS-04 of 04



Last Modified: 11 Jul 30, 2024 - 1:42PM

Associated Job Nos		Survey Data		Scales 0 1 2 3 4 5m Dimensions shown in metres except where shown otherwise	228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905				DMTR EVENT 22A ANNOTATED CROSS SECTIONS CONTROL LINE MC300110 - SHEET 1				Queensland Government		
Auxiliary Drg Nos		Horiz. Datum	GDA2020		Reference Points				ENGINEERING CERTIFICATION (RPEQ)				Job No.	2835872	
		Horiz. Grid	MGA 56		Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP	ENG. AREA	SIGNATORY FULL NAME	No.	DATE	Contract No.	CN-21784
1 50% Design Review		17.05.2024	Height Datum	AHD	PSM 44312	0.07	0.08	0.18	PSM 15677	CIVIL	MATT HAMILTON	16194	JULY 2024	Drawing No.	953868 3
Revisions/Descriptions		Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title	Date	Survey Books	Through Chainage from								Series Number	XS-09 of 11	





CENTRELINE DATA  
 E = 468508.579  
 N = 7174641.778  
 Z = 4.097

DATUM 2.00

DESIGN LEVELS					
STAGE 1 EARTHWORKS		6.651	4.053		6.377
EXISTING SURFACE		6.651	6.520	4.097	6.377
OFFSETS		-5.398	0.000	1.500	4.986

CHAINAGE 50.000

CENTRELINE DATA  
 E = 468505.401  
 N = 7174637.918  
 Z = 4.722

DATUM 3.00

DESIGN LEVELS					
STAGE 1 EARTHWORKS		6.867	4.678		6.615
EXISTING SURFACE		6.867	6.735	4.722	6.615
OFFSETS		-4.784	0.000	1.500	4.406

CHAINAGE 45.000

CENTRELINE DATA  
 E = 468514.935  
 N = 7174649.498  
 Z = 2.847

DATUM 1.00

DESIGN LEVELS							
STAGE 1 EARTHWORKS		6.290	2.803	2.847	2.823	5.954	5.942
EXISTING SURFACE		6.290	6.164	6.131	6.097	5.954	5.942
OFFSETS		-6.731	-1.500	0.000	1.500	6.197	10.589

CHAINAGE 60.000

CENTRELINE DATA  
 E = 468511.757  
 N = 7174645.638  
 Z = 3.472

DATUM 2.00

DESIGN LEVELS					
STAGE 1 EARTHWORKS		6.429	3.428	3.472	3.434
EXISTING SURFACE		6.429	6.296	6.243	6.205
OFFSETS		-6.002	-1.500	0.000	1.500

CHAINAGE 55.000



Last Modified: Jul 30, 2024 - 1:42PM

Revisions/Descriptions	Signatory: - RPEQ Full Name, Eng. Area and RPEQ No. or Full Name and Position Title	Date
3 100% Design Issue		19.07.2024
2 85% Design Review		07.06.2024
1 50% Design Review		17.05.2024

Associated Job Nos	Survey Data
	Horiz. Datum: GDA2020
	Auxiliary Drg Nos: Horiz. Grid: MGA 56
	Height Datum: AHD
	Survey Books: 200418 001, 200418

228 FRASER COAST REGIONAL COUNCIL 163 LAMINGTON BRIDGE - GYMPIE ROAD CTL CHGE 2824 - 2905				
Reference Points				
Preceding RP	Dist. to start of job (km)	From start to end of job	From end to Following RP	Following RP
PSM 44312	0.07	0.08	0.18	PSM 15677

DMTR EVENT 22A ANNOTATED CROSS SECTIONS CONTROL LINE MC300110 - SHEET 3			
ENGINEERING CERTIFICATION (RPEQ)			
ENG. AREA	SIGNATORY FULL NAME	No.	DATE
GEOTECH	GEMMA THOMAS	32011	JULY 2024
CIVIL	MATT HAMILTON	16194	JULY 2024

Queensland Government	
Job No.	2835872
Contract No.	CN-21784
Drawing No.	953870 3
Series Number	XS-11 of 11